

SECURITIES AND EXCHANGE COMMISSION OF PAKISTAN

BIDDING DOCUMENT PROCUREMENT OF WORKS

(For Smaller Contracts)

Renovation works at SECP's Companies Registration Office, Islamabad.

Table of Contents

INVIT	ATION FOR BIDS	4	
INSTE	RUCTIONS TO BIDDERS	6	
A. G	ENERAL	6	
IB.1	Scope of Bid	6	
IB.2	Source of Funds	6	
IB.3	Eligible Bidders	6	
IB.4	Cost of Bidding	6	
B. B	IDDING DOCUMENTS	6	
IB.5	Contents of Bidding Documents	6	
IB.6	Clarification of Bidding Documents	7	
IB.7	Amendment of Bidding Documents	7	
C.	PREPARATION OF BIDS	8	
IB.8	Language of Bid	8	
IB.9	Documents Comprising the Bid	8	
IB.10	Sufficiency of Bid	8	
IB.11	Bid Prices, Currency of Bid and Payment	9	
IB.12	Documents Establishing Bidder's Eligibility and Qualifications	9	
IB.13	Bid Security	9	
IB.14	Validity of Bids, Format, Signing and Submission of Bid	10	
D.	SUBMISSION OF Bid	10	
Instruc	etions to Bidders	16	
FORM	OF BID AND SCHEDULES TO BID	19	
LTB-1		20	
PREA	MBLE TO SCHEDULE OF PRICES	22	
Detaile	ed BOQ's	24	
Qualif	ication Criteria	25	
List of	Drawings	26	
Sampl	e Contract/Agreement	27	
Forma	t of Affidavit/Undertaking	Annex A	
	ration of Ultimate Beneficial Owners Information for Public Procurement Contracts ed BOQ'S	Annex B Annex C	
List of	Drawing	Annex D	
Specif	Specifications Anne		

INVITATION FOR BIDS



SECURITIES AND EXCHANGE COMMISSION OF PAKISTAN

T# 45/23-24

Invitation For Bid

The Securities & Exchange Commission of Pakistan (SECP) invites bids for the following:-

Renovation works at SECP's Companies Registration Office, Islamabad

Bidding document containing detailed terms and conditions, method of procurement, procedure for submission of bids, bid security, bid validity, opening of bid, evaluation criteria, clarification/rejection of bids etc. against above requirements are available for the interested bidders from the undersigned free of cost and can also be downloaded from https://www.secp.gov.pk/procurement/ OR https://eprocure.gov.pk/

Bidders must be registered with PEC/PCATP and the Federal Board of Revenue/Respective Revenue Boards for Income Tax and Sales Tax and must also be on the Active Taxpayers List.

Important: The bids should only be submitted through PPRA's **e-Pak Acquisition & Disposal System (EPADS)** i.e. https://eprocure.gov.pk/ on or before **May 17, 2024 by 1100Hrs** and will be opened on the same day at **1130Hrs**. (for any technical difficulty in using EPADS, prospective bidders may contact PPRA at https://www.ppra.org.pk/)

In case of any query, Admin Department may be contacted on Telephone Nos. 051-9195477 and 051-9195437 during office hours (Monday to Friday excluding public holidays)

Arshad Kamal, Additional Director (Admin)

NICL Building, 63 Jinnah Avenue, Blue Area, Islamabad

INSTRUCTIONS TO BIDDERS

INSTRUCTIONS TO BIDDERS

(Note: These Instructions to Bidders along with Bidding Data Sheet will not be part of the Contract and will cease to have effect once the contract is signed.)

A. GENERAL

IB.1 Scope of Bid

- 1.1 The Employer as defined in the Bidding Data Sheet hereinafter called "the Employer" wishes to receive bids for the construction and completion of works as described in these Bidding Documents, and summarized in the Bidding Data Sheet hereinafter referred to as the "Works".
- 1.2 Bidders must quote for the complete scope of work. Any Bid covering partial scope of work will be rejected as non-responsive.

IB.2 Source of Funds

2.1 The Employer has arranged funds from its own sources. [or any other source which may be indicated accordingly]

IB.3 Eligible Bidders

- 3.1 Bidding is open to all firms and persons meeting the following requirements:
 - a) duly licensed by the Pakistan Engineering Council (PEC) in the appropriate category for value of Works.

IB.4 Cost of Bidding

1.1 The bidders shall bear all costs associated with the preparation and submission of their respective bids and the Employer will in no case be responsible or liable for those costs, regardless of the conduct or outcome of the bidding process.

B. BIDDING DOCUMENTS

IB.5 Contents of Bidding Documents

5.1 In addition to invitation for bids, the bidding documents are those stated below and should be read in conjunction with any Addenda issued in accordance with Clause IB.6.1.

- 1. Instructions to Bidders & Bidding Data.
- 2. Form of Bid & Schedules to Bid Schedules to Bid comprise the following:
 - (i) Schedule A: Schedule of Prices
 - (ii) Schedule B: Specific Works Data
 - (iii) Schedule C: Works to be Performed by Subcontractors
 - (iv) Schedule D: Proposed Programme of Works
 - (v) Schedule E: Method of Performing Works
 - (vi) Schedule F: Integrity Pact
- 3. Conditions of Contract & Contract Data
- 4. Standard Forms:
 - (i) Form of Bid Security
 - (ii) Form of Performance Security
 - (iii) Form of Contract Agreement
 - (iv) Form of Bank Guarantee for Advance Payment
- 5. Specifications
- 6. Drawings, if any

IB.6 Clarification of Bidding Documents

- 6.1 A prospective bidder requiring any clarification(s) in respect of the Bidding Documents may notify the Engineer/Employer at the Employer's/Engineer's address indicated in the Bidding Data.
- 6.2 The Engineer/Employer will respond to any request for clarification which it receives earlier than ten (10) days prior to the deadline for the submission of Bids. Copies of the Engineer/Employer's response will be forwarded to all prospective bidders, at least five (5) days prior to dead line for submission of Bids, who have received the Bidding Documents including a description of the enquiry but without identifying its source enquiring any clarification (s) in respect of the Bidding Documents may notify the Employer in writing at the Employer's address indicated in the Invitation for Bids. The Employer will respond to any request for clarification which he receives earlier than 5 days prior to the deadline for submission of bids.

Copies of the Employer's response will be forwarded to all purchasers of the Bidding Documents, including a description of the enquiry but without identifying its source.

IB.7 Amendment of Bidding Documents

7.1 At any time prior to the deadline for submission of bids, the Employer may, for any reason, whether at his own initiative or in response to a clarification

requested by a prospective bidder, modify the Bidding Documents by issuing addendum.

- 7.2 Any addendum thus issued shall be part of the Bidding Documents pursuant to Sub-Clause 6.1 hereof and shall be communicated in writing to all purchasers of the Bidding Documents. Prospective bidders shall acknowledge receipt of each addendum in writing to the Employer.
- 7.3 To afford prospective bidders reasonable time in which to take an addendum into account in preparing their bids, the Employer may extend the deadline for submission of Bids.

C. PREPARATION OF BIDS

IB.8 Language of Bid

8.1 The bid prepared by the bidder and all correspondence and documents relating to the Bid, exchanged by the bidder and the Employer shall be written in the English language, provided that any printed literature furnished by the bidder may be written in another language so long as accompanied by an English translation of its pertinent passages in which case, for purposes of interpretation of the Bid, the English translation shall govern.

IB.9 Documents Comprising the Bid

- 9.1 The bid prepared by the bidder shall comprise the following components:
 - a) Covering Letter
 - b) Form of Bid duly filled, signed and sealed, in accordance with Sub-Clause IB.14.3.
 - c) Schedules (A to F) to Bid duly filled and initialed, in accordance with the instructions contained therein & in accordance with Sub-Clause IB14.3.
 - d) Bid Security furnished in accordance with Clause IB.13.
 - e) Power of Attorney in accordance with Sub-Clause IB 14.5.
 - f) Documentary evidence in accordance with Clause IB.11
 - g) Documentary evidence in accordance with Clause IB.12.

IB.10 Sufficiency of Bid

10.1 Each bidder shall satisfy himself before Bidding as to the correctness and sufficiency of his Bid and of the rates and prices entered in the Schedule of Prices, which rates and prices shall except in so far as it is otherwise expressly provided in the Contract, cover all his obligations under the Contract and all matters and things necessary for the proper completion of the Works.

10.2 The bidder is advised to obtain for himself at his own cost and responsibility all information that may be necessary for preparing the bid and entering into a Contract for execution of the Works.

IB.11 Bid Prices, Currency of Bid and Payment

- 11.1 The bidder shall fill up the Schedule of Prices (Schedule A to Bid) indicating the unit rates and prices of the Works to be performed under the Contract. Prices in the Schedule of Prices shall be entered keeping in view the instructions contained in the Preamble to Schedule of Prices.
- 11.2 Unless otherwise stipulated in the Conditions of Contract, prices quoted by the bidder shall remain fixed during the bidder's performance of the Contract and not subject to variation on any account.
- 11.3 The unit rates and prices in the Schedule of Prices shall be quoted by the bidder in the currency as stipulated in Bidding Data.

IB.12 Documents Establishing Bidder's Eligibility and Qualifications

- 12.1 Pursuant to Clause IB.8, the bidder shall furnish, as part of its bid, documents establishing the bidder's eligibility to bid and its qualifications to perform the Contract if its bid is accepted.
- 12.2 Bidder/Manufacturer must possess and provide evidence of its capability and the experience as stipulated in Bidding Data and the Qualification Criteria stipulated in the Bidding Documents.

IB.13 Bid Security

- 13.1 Each bidder shall furnish, as part of his bid, at the option of the bidder, a Bid Security in the amount stipulated in Bidding Data in Pak. Rupees in the form of Deposit at Call or a Bank Guarantee issued by a Scheduled Bank in Pakistan or an insurance company having at least AA rating from PACRA/JCR in favour of the Employer valid for a period up to twenty eight (28) days beyond the bid validity date.
- 13.2 Any bid not accompanied by an acceptable Bid Security shall be rejected by the Employer as non-responsive.
- 13.3 The bid securities of unsuccessful bidders will be returned upon award of contract to the successful bidder or on the expiry of validity of Bid Security whichever is earlier.
- 13.4 The Bid Security of the successful bidder will be returned when the bidder has furnished the required Performance Security, pursuant to Clause IB.21 and signed the Contract Agreement, pursuant to Sub-Clauses IB.20.2 & 20.3.
- 13.5 The Bid Security may be forfeited:
 - a) if a bidder withdraws his bid during the period of bid validity; or
 - b) if a bidder does not accept the correction of his Bid Price, pursuant to Sub-Clause 16.4 (b) hereof; or
 - c) in the case of a successful bidder, if he fails to:

- (i) furnish the required Performance Security in accordance with Clause IB.21, or
- (ii) sign the Contract Agreement, in accordance with Sub-Clauses IB.20.2 & 20.3.

IB.14 Validity of Bids, Format, Signing and Submission of Bid

- 14.1 Bids shall remain valid for the period stipulated in the Bidding Data after the date of bid opening.
- 14.2 All Schedules to Bid are to be properly completed and signed.
- 14.3 No alteration is to be made in the Form of Bid except in filling up the blanks as directed. If any alteration be made or if these instructions be not fully complied with, the bid may be rejected.
- 14.4 Each bidder shall prepare Original and number of copies specified in the Bidding Data of the documents comprising the bid as described in Clause IB.8 and clearly mark them "ORIGINAL" and "COPY" as appropriate. In the event of discrepancy between them, the original shall prevail.
- 14.5 The original and all copies of the bid shall be typed or written in indelible ink and shall be signed by a person or persons duly authorized to sign (in the case of copies, Photostats are also acceptable). This shall be indicated by submitting a written Power of Attorney authorizing the signatory of the bidder to act for and on behalf of the bidder. All pages of the bid shall be initialed and official seal be affixed by the person or persons signing the bid.
- 14.6 The Bid shall be delivered in person or sent by registered mail at the address to Employer as given in Bidding Data.

D. SUBMISSION OF Bid

IB.15 Deadline for Submission, Modification & Withdrawal of Bids

- 15.1 Bids must be received by the Employer at the address/provided in Bidding Data not later than the time and date stipulated therein.
- 15.2 Bids submitted through telegraph, telex, fax or e-mail shall not be considered.
- 15.3 Any bid received by the Employer after the deadline for submission prescribed in Bidding Data will be returned unopened to such bidder.
- 15.4 Any bidder may modify or withdraw his bid after bid submission provided that the modification or written notice of withdrawal is received by the Employer prior to the deadline for submission of bids.

15.5 Withdrawal of a bid during the interval between the deadline for submission of bids and the expiration of the period of bid validity specified in the Form of Bid may result in forfeiture of the Bid Security pursuant to Sub-Clause IB.13.5 (a).

E BID OPENING AND EVALUATION

IB. 16 Bid Opening, Clarification and Evaluation

- 16.1 The Employer will open the bids, in the presence of bidders' representatives who choose to attend, at the time, date and location stipulated in the Bidding Data.
- 16.2 The bidder's name, Bid Prices, any discount, the presence or absence of Bid Security, and such other details as the Employer at its discretion may consider appropriate, will be announced by the Employer at the bid opening. The Employer will record the minutes of the bid opening. Representatives of the bidders who choose to attend shall sign the attendance sheet.
- 16.3 Any Bid Price or discount which is not read out and recorded at bid opening will not be taken into account in the evaluation of bid.
- 16.4 To assist in the examination, evaluation and comparison of Bids the Engineer/Employer may, at its discretion, ask the bidder for a clarification of its Bid. The request for clarification and the response shall be in writing and no change in the price or substance of the Bid shall be sought, offered or permitted.
 - a) Prior to the detailed evaluation, pursuant to Sub-Clauses IB.16.7 to 16.9, the Engineer/Employer will determine the substantial responsiveness of each bid to the Bidding Documents. For purpose of these Clauses, a substantially responsive bid is one which conforms to all the terms and conditions of the Bidding Documents without material deviations. It will include to determine the requirements listed in Bidding Data.
 - b) Arithmetical errors will be rectified on the following basis:

If there is a discrepancy between the unit price and total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail and the total price shall be corrected. If there is a discrepancy between the words and figures the amount in words shall prevail. If there is a discrepancy between the Total Bid price entered in Form of Bid and the total shown in Schedule of Prices-Summary, the amount stated in the Form of Bid will be corrected by the Employer in accordance with the Corrected Schedule of Prices.

If the bidder does not accept the corrected amount of Bid, his Bid will be rejected and his Bid Security forfeited.

- 16.5 A Bid determined as substantially non-responsive will be rejected and will not subsequently be made responsive by the bidder by correction of the non- conformity.
- 16.6 Any minor informality or non-conformity or irregularity in a Bid which does not constitute a material deviation may be waived by Employer, provided such waiver does not prejudice or affect the relative ranking of any other bidders.

16.7 The Engineer/Employer will evaluate and compare only the bids previously determined to be substantially responsive pursuant to Sub-Clauses IB.16.4 to

16.6 as per requirements given hereunder. Bids will be evaluated for complete scope of works. The prices will be compared on the basis of the Evaluated Bid Price pursuant to Sub-Clause 16.8 herein below.

a) Technical Evaluation

It will be examined in detail whether the Works offered by the bidder complies with the Technical Provisions of the Bidding Documents. For this purpose, the bidder's data submitted with the bid in Schedule B to Bid will be compared with technical features/criteria of the Works detailed in the Technical Provisions. Other technical information submitted with the bid regarding the Scope of Work will also be reviewed.

b) Commercial Evaluation

It will be examined in detail whether the bids comply with the commercial/contractual conditions of the Bidding Documents. It is expected that no material deviation/stipulation shall be taken by the bidders.

16.8 Evaluated Bid Price

In evaluating the bids, the Engineer/Employer will determine for each bid in addition to the Bid Price, the following factors (adjustments) in the manner and to the extent indicated below to determine the Evaluated Bid Price:

- (i) making any correction for arithmetic errors pursuant to Sub-Clause 16.4 hereof.
- (ii) making an appropriate price adjustment for any other acceptable variation or deviation.
- (iii) making an appropriate price adjustment for Deviations in terms of Payments (if any and acceptable to the Employer).
- (iv) discount, if any, offered by the bidders as also read out and recorded at the time of bid opening.

16.9 Evaluation Methods

Pursuant to Sub-Clause 16.8, Para (ii), and (iii) following evaluation methods for price adjustments will be followed:

(i) Price Adjustment for Technical Compliance

The cost of making good any deficiency resulting from technical non-compliance will be added to the Corrected Total Bid Price for comparison purposes only. The adjustments will be applied taking the highest price quoted by other bidders being evaluated in detail in their original Bids for corresponding item. In case of non-availability of price from other bidders, the price will be estimated by the Engineer/Employer.

(ii) Price Adjustment for Commercial Compliance

The cost of making good any deficiency resulting from any quantifiable variations and deviations from the Bid Schedules and Conditions of

Contract, as determined by the Engineer/Employer will be added to the Corrected Total Bid Price for comparison purpose only. Adjustment for commercial compliance will be added to the Corrected Total Bid Prices.

(iii) Price Adjustment for Deviation in Terms of Payments

Refer to Bidding Data

IB.17 Process to be Confidential

- 17.1 Subject to Sub-Clause IB.16.3 heretofore, no bidder shall contact Engineer/Employer on any matter relating to its Bid from the time of the Bid opening to the time the bid evaluation result is announced by the Employer. The evaluation result shall be announced at least ten (10) days prior to award of Contract. The announcement to all bidders will include table(s) comprising read out prices, discounted prices, price adjustments made, final evaluated prices and recommendations against all the bids evaluated.
- 17.2 Any effort by a bidder to influence Engineer/Employer in the Bid evaluation, Bid comparison or Contract Award decisions may result in the rejection of his Bid. Whereas, any bidder feeling aggrieved may lodge a written complaint not later than fifteen (15) days after the announcement of the bid evaluation result, however, mere fact of lodging a complaint shall not warrant suspension of procurement process.

F. AWARD OF CONTRACT

IB.18 Post Qualification

- 18.1 The Employer, at any stage of the bid evaluation, having credible reasons for or prima facie evidence of any defect in supplier's or contractor's capacities, may require the suppliers or contractors to provide information concerning their professional, technical, financial, legal or managerial competence whether already pre-qualified or not:
 - Provided that such qualification shall only be laid down after recording reasons therefor in writing. They shall form part of the records of that bid evaluation report.
- 18.2 The determination will take into account the bidder's financial and technical capabilities. It will be based upon an examination of the documentary evidence of the bidders' qualifications submitted under Clause IB.11, as well as such other information required in the Bidding Documents.

IB.19 Award Criteria & Employer's Right

19.1 Subject to Sub-Clause IB.19.2, the Employer will award the Contract to the bidder whose bid has been determined to be substantially responsive to the Bidding Documents and who has offered the lowest evaluated Bid Price, provided that such bidder has been determined to be qualified to satisfactory perform the Contract in accordance with the provisions of Clause IB.18.

19.2 Not with standing Sub-Clause IB.19.1, the Employer reserves the right to accept or reject any bid, and to annul the bidding process and reject all bids, at any time prior to award of Contract, without thereby incurring any liability to the affected bidders or any obligation to inform the affected bidders of the grounds for the Employer's action except that the grounds for its rejection of all bids shall upon request be communicated, to any bidder who submitted a bid, without justification of the grounds. Notice of the rejection of all the bids shall be given promptly to all the bidders.

IB.20 Notification of Award & Signing of Contract Agreement

- 20.1 Prior to expiration of the period of bid validity prescribed by the Employer, the Employer will notify the successful bidder in writing ("Letter of Acceptance") that his Bid has been accepted.
- 20.2 Within seven (7) days from the date of furnishing of acceptable Performance Security under the Conditions of Contract, the Employer will send the successful bidder the Form of Contract Agreement provided in the Bidding Documents, incorporating all agreements between the parties.
- 20.3 The formal Agreement between the Employer and the successful bidder shall be executed within seven (7) days of the receipt of Form of Contract Agreement by the successful bidder from the Employer.

IB.21 Performance Security

- 21.1 The successful bidder shall furnish to the Employer a Performance Security in the form and the amount stipulated in the Bidding Data Sheet and the Conditions of Contract within a period of fourteen (14) days after the receipt of Letter of Acceptance.
- 21.2 Failure of the successful bidder to comply with the requirements of Sub-Clauses IB.20.2 & 20.3 or 21.1 or Clause IB.22 shall constitute sufficient grounds for the annulment of the award and forfeiture of the Bid Security.

IB.22 Integrity Pact

The Bidder shall sign and stamp the Form of Integrity Pact provided at Schedule-F to Bid in the Bidding Document for all Federal Government procurement contracts exceeding Rupees ten (10) million. Failure to provide such Integrity Pact shall make the bid non-responsive.

BIDDING DATA SHEET

Bidding Data Sheet

INSTRUCTIONS TO BIDDERS

1.1 Name of Employer:

Securities and Exchange Commission of Pakistan (SECP) 63-NICL Building, Blue Area, Islamabad

The Employer's Representative is:

Mr. Zahid ul Hassan

Deputy Director (Admin) Securities and Exchange Commission of Pakistan (SECP) 63-NICL Building, Blue Area, Islamabad 051-9195302

1.2 Time for completion

30 working days

2.1 Brief Description of Works:

Renovation works at CRO Islamabad of SECP head office Islamabad as per BOQ

2.1(b) Basic Eligibility (mandatory Requirements)

The firms/ companies fulfilling the following basic requirements shall be considered for further evaluation (relevant documents to be attached):

- a) Valid Registration with PEC in Category "C-6 or above" for the local firms on the date of bid opening.
- b) Only registered supplier/service providers/contractors who are on Active Taxpayers List (Income and Sales Tax) of FBR/respective revenue boards are only eligible to supply goods/provide services to the Commission. Bids of all those who are not registered with the Federal Board of Revenue/Respective Revenue Boards for Income Tax and Sales Tax shall be rejected.
- c) In case bidder (if selected) is not in ATL at the time of payment then the payment shall be stopped till he files his mandatory returns and appears on ATL of FBR OR whole of the tax involved or as applicable to supplies on the basis of gross value of supplies shall be deducted.
- d) Declaration of Ultimate Beneficial Owners Information as per Annex-B
- e) Bidder must submit affidavit/undertaking (on stamp paper of Rs.100) duly notarized, failing which the bid shall be rejected, format is available at Annex-A.
- f) Submission of duly signed and initialed copy of Tender Document along with Appendices, Annexures & Attachments refereed therewith. Signing and stamping shall mean validation and compliance to all the details included in Tender Document.

- g) Bidder to confirm that the Time of Completion of the Project shall be within 30 working days from the date of Award of Contract. Bidder shall provide an undertaking that Bidder(s) have proven available resources to implement and complete the project on fast track basis within Time of Completion.
- h) Bid submitted ONLY through PPRA's e-Pak Acquisition & Disposal System (EPADS) shall be considered for further processing.
- i) Method: Single Stage Two Envelop Method
- 5.1 (a) Employer's address:

Securities and Exchange Commission Pakistan (SECP) 63-NICL Building, Blue Area, Islamabad

Phone No.: 051-9195302

Email: zahid.hassan@secp.gov.pk

- 10.3 Bid shall be quoted entirely in Pak Rupees. The payment shall be made in Pak. Rupees.
- 11.2 The bidder has the financial and technical capability necessary to perform the Contract as follows. The bid will be evaluated as following criteria to ascertain "Technical Responsive" bidder. The applicant securing at least 70% Marks i.e. 35 out of 50, will be declared Technically Responsive. The financial proposal of only Technically Responsive Bidder will be considered for opening, Arithmetical Correctness and Financial Comparison. The "Technically Responsive and Most Advantageous Bidder i.e. lowest" will be awarded the contract.

Sr. No.	Category	Weightage / Marks
a)	PEC registration in C-6 or above	Must Requirement
b)	Tax return of the last three years along with company bank statement of one year	Must Requirement
c)	Experience Record	50

a. Experience record

Sr. No.	Description	Max Marks
	Completed Projects	
1.	Experience in the execution of five (5) projects of renovation/civil work of a similar nature of Rs. 7.0 million or above. (06 marks for each project, maximum marks are 30). Projects completed during the last 10 years will be considered for evaluation.	30
2.	In-hand Projects - If the firm has five or more projects in hand: (04 marks for each project, maximum marks are 20).	20
	- If the firm has less than five projects in hand, (10 marks shall be awarded).	

Total For Experience Record: 50	
---------------------------------	--

Note: The Applicant shall attach evidence of Work Orders/ Letter of Acceptance or Completion Certificate for completed projects.

13.1 Amount of Bid Security

Bid security an amount of PKR= 200,000/- in the form of pay order/ demand draft/CDR issued by scheduled bank of Pakistan in favour of Securities and Exchange Commission of Pakistan (SECP).

Pre-bid meeting: pre bid meeting shall be withheld at Companies registration office on May 08, 2024 at 1430Hrs at following address;

1st floor, state life building no. 7, nazim Uddin road blue area Islamabad.

14.1 **Period of Bid Validity**

Bid shall remain valid for 90 days.

14.4 Number of Copies of the Bid to be submitted

ONE and only though EPADS.

14.6 (a) Employer's Address for the Purpose of Bid Security Submission

M. Ubaidullah Khalid

Additional Joint Director (Admin)

Securities and Exchange Commission Pakistan

NIC Building, 63 Jinnah Avenue Islamabad

Phone No.: 051- 9195302/051-9195437

15.1 **Deadline for Submission of Bids**

As per IFB

16.1 Venue, Time, and Date of Bid Opening

As per IFB

Time and Date of Bid Opening: As per IFB

16.4 **Responsiveness of Bids**

- (i) the Bid is valid till required period
- (ii) the Bid prices are firm during currency of contract (if it is a fixed price bid)
- (iii) completion period offered is within specified limits,
- (iv) the Bidder/Manufacturer is eligible to Bid and possesses the requisite experience, capability and qualification.
- (v) the Bid does not deviate from basic technical requirements and
- (vi) the Bids are generally in order, etc.
- (vii) Technically responsive and lowest evaluated Bid
- (Viii) Bids are submitted only through EPADS...Hard copy is not acceptable.
- (ix) Copy of Bid Security uploaded with Technical Bid.
- (x) Original Bid Security received to SECP Head Office before deadline of bid submission. All bids must be accompanied by a scanned copy of Bid Security in the form of Banker's Cheque i.e. Pay Order in the amount of Rs.200,000. The ORIGINAL Bid Security

 (18)

in favor of SECP must be submitted to the procuring agency any time before the closing time of bid submission, failing which the bid shall be rejected.

16.9 **Price Adjustment**

Deleted

FORM OF BID AND SCHEDULES TO BID

Letter of Technical Bid

Name of Contract: "Renovation works at SECP's Companies Registration Office, Islamabad

To: M. Ubaidullah Khalid

Additional Joint Director (Admin)

Securities and Exchange Commission Pakistan NIC Building, 63 Jinnah Avenue Islamabad

We, the undersigned, declare that:

- (a) We have examined and have no reservations to the Bidding Documents, including Addenda issued in accordance with Instructions to Bidders (IB) 9;
- (b) We offer to execute and complete in conformity with the Bidding Documents the following Works:

Renovation works at CRO Islamabad of SECP Head Office

- (c) Our Bid consisting of the Technical Bid and the Price Bid shall be valid for a period of ninety (90) days from the date fixed for the bid submission deadline in accordance with the Bidding Documents, and it shall remain binding upon us and may be accepted at any time before the expiration of that period;
- (d) As security for due performance of the under takings and obligations of our bid, we submit here with a Bid security, in the amount specified in Bidding Data Sheet, which is valid 148 days.
- (e) We are not participating, as a Bidder or as a subcontractor, in more than one bid in this bidding process, other than alternative offers submitted in accordance with IB16 (as applicable).
- (f) We agree to permit Employer or its representative to inspect our accounts and records and other documents relating to the bid submission and to have them audited by auditors. This permission is extended for verification of any information provided in our Technical Bid which comprises all documents enclosed herewith in accordance with IB.11.1 of the Bidding Data Sheet.

Name	
In the capacity of	
Signed	
Duly authorized to sign the Bid for and on behalf of	Date
Address	

SCHEDULES TO BID INCLUDE THE FOLLOWING:

• Schedule A to Bid: Schedule of Prices

• Schedule B to Bid: Qualification Criteria

• Schedule C to Bid: List of Drawing(s)

PREAMBLE TO SCHEDULE OF PRICES

1. GENERAL

- 1.1 The Schedule of Prices shall be read in conjunction with the Conditions of Contract, Contract Data together with the Specifications and Drawings, if any.
- 1.2 The Contract shall be for the whole of the Works as described in these Bidding Documents. Bids must be for the complete scope of works.

2. DESCRIPTION

2.1 The general directions and descriptions of works and materials are not necessarily repeated nor summarized in the Schedule of Prices. References to the relevant sections of the Bidding Documents shall be made before entering prices against each item in the Schedule of Prices.

3. UNITS & ABBREVIATIONS

3.1 Units of measurement, symbols and abbreviations expressed in the Bidding Documents shall comply with the System International d' Unites (SI Units).

4. RATES AND PRICES

- 4.1 Except as otherwise expressly provided under the Conditions of Contract, the rates and amounts entered in the Schedule of Prices shall be the rates at which the Contractor shall be paid and shall be the full inclusive value of the works set forth or implied in the Contract; except for the amounts reimbursable, if any to the Contractor under the Contract.
- 4.2 Unless otherwise stipulated in the Contract Data, the rates and prices entered by the bidder shall not be subject to adjustment during the performance of the Contract.
- 4.3 All duties, taxes and other levies payable by the Contractor shall be included in the rates and prices.
- 4.4 The whole cost of complying with the provisions of the Contract shall be included in the items provided in the Schedule of Prices, and where no items are provided, the cost shall be deemed to be distributed among the rates and prices entered for the related items of the Works and no separate payment will be made for those items.

The rates, prices and amounts shall be entered against each item in the Schedule of Prices. Any item against which no rate or price is entered by the bidder will not be paid for by the Employer when executed and shall be deemed covered by the rates and prices for other items in the Schedule of Prices.

- 4.5 (a) The bidder shall be deemed to have obtained all information as to and all requirements related thereto which may affect the bid price.
 - (b) The Contractor shall be responsible to make complete arrangements for the transportation of the Plant to the Site.
- 4.6 The Contractor shall provide for all parts of the Works to be completed in every respect. Notwithstanding that any details, accessories, etc. required for the complete installation and satisfactory operation of the Works, are not specifically mentioned in the Specifications, such details shall be considered as included in the Contract Price.

5. BID PRICES

5.1 Break-up of Bid Prices

The various elements of Bid Prices shall be quoted as detailed by the Employer in the format of Schedule of Prices.

The bidder shall recognize such elements of the costs which he expects to incur the performance of the Works and shall include all such costs in the rates and amounts entered in the Schedule of Prices.

5.2 Total Bid Price

The total of bid prices in the Schedule of Prices shall be entered in the Summary of Bid Prices.

6. PROVISIONAL SUMS

Provisional Sums included and so designated in the Schedule of Prices if any, shall be expended in whole or in part at the direction and discretion of the Engineer/Employer. The Contractor will only receive payment in respect of Provisional Sums if he has been instructed by the Engineer/Employer to utilize such sums..

DETAILED BOQ'S attached as Annex C of this document

QUALIFICATION CRITERIA

The bidder has the financial and technical capability necessary to perform the Contract as follows. The bid will be evaluated as following criteria to ascertain "Technical Responsive" bidder. The applicant securing at least 70% Marks i.e. 35 out of 50, will be declared Technically Responsive. The financial proposal of only Technically Responsive Bidder will be considered for opening, Arithmetical Correctness and Financial Comparison. The "Technically Responsive and Most Advantageous Bidder i.e. lowest" will be awarded the contract.

Sr. No.	Category	Weightage / Marks
a)	PEC registration in C-6	Must Requirement
b)	Tax return of the last three years along with company bank statement of one year must be attached	Must Requirement
c)	Experience Record	50

b. Experience record

Sr. No.	Description	Max Marks
	Completed Projects	
1.	Experience in the execution of five (5) projects of renovation/civil work of a similar nature of Rs. 7.0 million or above. (06 marks for each project, maximum marks are 30). Projects completed during the last 10 years will be considered for evaluation.	30
	In-hand Projects	
2.	If the firm has five or more projects in hand: (04 marks for each project, maximum marks are 20). If the firm has less than five projects in hand, 10 marks shall be awarded,	20
	Total For Experience Record:	50

Note:

- a). The Applicant shall attach evidence of Work Orders/ Letter of Acceptance/Contract Agreement or Completion Certificate for completed projects in public sector. The Employer may request for additional information i.e bank transaction as documentary evidence in case of private sector projects.
- b). The firm meeting must requirement shall be considered eligible for technical evaluation only.

Schedule-C to Bid

LIST OF DRAWINGS- Annex D of this document

(to be signed by the Bidder)

Sample Agreement

This agreement ("Agreement") is made on this the ——— day of -----at Islamabad.

BY AND BETWEEN

Securities & Exchange Commission of Pakistan, a statutory body established in pursuance of the Securities and Exchange Commission of Pakistan Act, 1997 with its head office located at **NIC Building, 63 Jinnah Avenue, Islamabad** (the "Commission", which expression shall, where the context so admits, include its successors in interest and permitted assigns) of the One Part

AND

Commission and the Contractor shall hereinafter be referred to as the "Parties" collectively and the "Party" individually and interchangeably.

WHEREAS:

- 1. The Commission is desirous to renovate its companies registration office of the SECP head office Islamabad.
- 2. The Contractor represents and warrants that it has the relevant expertise and adequate skills to provide the Services required by the Commission.
- 3. The Commission has approved and the Contractor has agreed to the provision and installation of all materials, labor and expertise to perform the Services described in the attached schedule as mentioned in (BOQ/TORs) Annexure "A".
- 4. The Contractor represents that it can execute the same as per Specifications in (BOQ/TORs) Annexure "A" and to complete the work renovating the Premises on the terms and conditions set out hereunder.

Now Therefore it is Agreed Between The Parties as Follows:

The recital hereof shall form an integral part of this Agreement.

<u>ARTICLE 1– DEFINITION AND INTERPRETATION</u>

For the purposes of this Agreement, the following terms shall have the meaning set out herein, unless the context requires otherwise.

- a. "Agreement" means this agreement datedalong with its Annexure and Appendices.
- b. "Premises" CRO office of the Commission Head Office at NICL Building, Islamabad.
- c. "Specifications" means the description of materials and details of renovation work as outlined in (BOQ/TORs) Annexure "A" attached hereto and approved by the Commission.
- d. "Services" bears the meaning attributed thereto in clause 2.1.
- e. "Consultant" means the consultant appointed by the Commission for the subject purpose.

In this Agreement any reference to an Article, a Schedule or an Appendix shall be a reference to an Article, Schedule or Appendix of this Agreement. The Services under this Agreement is for the Contractor to renovate the CRO office, etc (if any), erection of wood and wooden partitions, tiles, installation of doors, electric / power related wiring and other works as mentioned in the BOQ. The Contractor shall ensure that all or any Services shall be in accordance with the approved (BOQ/TORs) Annexure-A and to the satisfaction of the Commission.

ARTICLE 2-PRICE

In consideration of the performance by the "CONTRACTOR" of its obligations under this Agreement to the satisfaction of the Commission, the Agreement price ("Price") to be paid to the Contractor shall be Rs-----------------Inclusive of all Applicable Govt. Taxes and duties but not limited to excise duty, Sales tax, or any other taxes or levies). All Services shall be executed/supplied as Turn Key Job as per (BOQ/TORs) Annexure "A" and design layout as per drawings provided by the Commission".

- a) All payment will be subjected to withholding tax deductions at source as per regulations, if relevant.
- b) Any and all payments made under this Agreement shall be less any Government taxes, which the Commission is by law required to deduct.
- c) Final payment shall be made based on the actual Measurement book prepared by the contractor and approved by the Project Director.
- **d)** No advance payment shall be made. Payment terms would be as follows;
- e) 25% payment upon completion of electrical/voice and other cabling laying down
- f) 25% payment upon completion of the installation of tiles and completion of furniture items on the premises

g) Balance payment upon completion of the work and handing over site to the Commission

<u>ARTICLE 3 – PERFORMANCE GUARANTEES</u>

- a) The Contractor shall ensure that only such materials as shall be of the respective kinds described in the design and (BOQ/TORs) shall be approved and only such workmanship as conforms with the Design. The contractor will ensure that all material used for renovation is fit for the purpose it is intended, is free from defects. The Contractor shall arrange samples of all relevant materials and get its approval from the Consultant of the Commission. 10% amount of each invoice amount shall be retained for 6 months period as retention period.
- b) The Services shall be completed and the Premises handed over to the Commission within a maximum period of 30 days. however, the Commission shall have a right to make a deduction from the Agreement price @ 2,000/- (Rupees five thousand only) for every day of delay.
- c) If the project could not be completed in maximum 20 days from the execution date of the Agreement due to delay of payments, approvals or any other reason caused by the Commission, then the charge specified in Article shall be waived off.

ARTICLE 4 – ADDRESSES OF THE PARTIES

The authorized representatives of both Parties along with their addresses are as follows.

Commission: Securities & Exchange Commission of Pakistan NICL Building, Blue Area, Islamabad.

Attention	Mr. Zahid Ul Hassan Deputy Director (Admin)
~	
Contractor:	
Attention:	

ARTICLE 5 - TERMINATION BY THE CONTRACTOR

If the Coordinator fails to issue a payment certificate for a period of thirty days through no fault of the Contractor, or if the Client fails to make payment thereon for a period of thirty days from the issuance of a payment certificate, the Contractor may, upon fourteen days' written notice to the Client, terminate the Contract, provided however, that Client shall first have an opportunity to remit such payment within the fourteen day period following written notice.

TERMINATION BY THE CLIENT:

If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents or fails to perform any provision of the Contract, the Client may, after Seven days' written notice to the Contractor and without prejudice to any other remedy Client may have, make good such deficiencies and may deduct the cost thereof from the payment then or thereafter due the Contractor or, at Client's option, may terminate Contractor's work under the Contract and take possession of the site and of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor and may finish the Work by whatever method Client may deem expedient, and if the unpaid balance of the Contract Sum exceeds the expense of finishing the Work, such excess shall be paid to the Contractor, but if such expense exceeds such unpaid balance, the Contractor shall pay the difference to the Client. These rights and remedies are in addition to any right to damages or other rights and remedies allowed by law.

ARTICLE 6 – DISPUTE RESOLUTION

- a) **Amicable settlement.** The Parties shall use their best efforts to amicably settle all disputes arising out of or in connection with this Agreement.
- b) **Dispute settlement.** Any dispute between the Parties arising under this Agreement, which cannot be amicably settled within thirty (30) days after receipt by one Party of the other Party's request for such amicable settlement, may be submitted by either Party for settlement in accordance with the provisions of the Arbitration Act, 1940 (Act No. X of 1940). Any Services to be performed under the Agreement shall, if reasonably practicable, continue during the arbitration proceedings and no payment due to or by the Commission shall be withheld on account of such arbitration proceedings. The matter shall be referred to a sole arbitrator as agreed by both Parties. The seat of arbitration shall be Islamabad, Pakistan and the language of arbitration shall be English. In case the Parties do not agree to the appointment of the arbitrator, the same shall be appointed by the court of competent jurisdiction.

ARTICLE 7 - MISCELLANEOUS

- a) The Contractor shall make its own arrangements for the engagement of all staff and labor necessary for the fulfillment of its obligations under this Agreement, and for their payment, feeding and transport. Whereas Commission allows to work Labor from 5pm till 12:00 p.m. Contractors labor will not be allowed to stay in Client Premises after above mentioned time except one Security Guards to safeguard the Contractors construction material of all type. Client will not be responsible of any claim in case of any theft, misplace of any material of the contractor. Contractor labor will not be allowed to move at any other place except site only at Client Premises".
- b) Contractor agrees to protect, indemnify, defend and hold harmless the Commission, its Chairman, Commissioners and employees from any claims, demands obtained by the Contractor's staff, labor or its employees, on account of personal injury or death.

- c) The copyright of all document prepared by the Contractor in connection with the Agreement rests with the Commission. The Contractor shall not be entitled either directly or indirectly to make use of these documents for carrying out work other than that required by the terms of this Agreement. Contractors will submit all such kind of documents to the client SECP on completion of the project at the time of handing over.
- d) The Contractor shall maintain confidentially in all matters arising out of this Agreement and which are not in the public domain for a period of five (5) years from the date of execution of this Agreement.
- e) The Contractor shall deliver to the Commission all as built drawings and relevant warranties (wherever applicable) for equipment upon handing over of the Premises.
- f) The Commission shall be responsible for paying all the Utility Bills (Electricity or Backup and water supply etc.) of the ---- floor for the whole time period of renovation which shall not be misused by the Contractor or its personnel.
- g) The project plan will be submitted before start of work and a weekly update report shall be submitted to the Project Director.
- h) Lead time items procurement will be done well in advance and the ordering plan will be submitted to the Client.
- i) Prove of all procurements will be produced at the request of the client.
- j) Any changes or alternations in plan or material etc will be obtained in writing from the client.

ARTICLE 8 – ACTIONS ON BEHALF OF CLIENT

The Contractor shall take no action on behalf of the Commission in the performance of Services under

this Agreement or conduct any operations relating thereto that would subject either Party to liability or

penalty under any law, rules, regulation, or decrees by any Government or Authority.

<u>ARTICLE 9 – FORCE MAJEURE</u>

Neither Party shall make claim against the other Party or be deemed to be in breach of Agreement where

such failure or omission is caused by Force Majeure. Force Majeure shall include, but not be limited to.

Acts of God, war (declared or undeclared), insurrection, acts of terrorists, acts of governments or

government bodies (including legislative bodies, courts and executive officers of agencies), unusually

severe weather during the period in question,. Or any other similar matters beyond the control of or

which could not have been reasonably foreseen and / or avoided by the Party affected.

<u>ARTICLE 10 – ENTIRETY AND COUNTERPARTS</u>

- This Agreement including any supplement and all Appendices and Annexures hereto constitute the
- entire Agreement between the Parties with respect to the subject matter hereof and shall supersede all
- promises and representations made by one Party to the other concerning the obligations to be performed
- hereunder. This Agreement may not be discharged, released, supplemented, amended or modified in
- any manner except by an instrument in writing signed by a duly authorized representative of both the
- Parties. This Agreement shall be executed in two counterparts, both of which shall be deemed original.

<u>ARTICLE 11 – RELATIONSHIP</u>

The Parties hereby agree that no terms of this Agreement shall be construed as to portray an employer-employee relationship between the Parties and that both the Parties are acting independently and at their discretion.

ARTICLE 12 – APPLICABLE LAW AND JURISDICTION

This Agreement is governed by the laws of the Islamic Republic of Pakistan. Disputes arising out of

this Agreement are subject to the exclusive jurisdiction of the courts of Islamabad, to which the

Parties irrevocably submit.

ARTICLE 13 – PROJECT COORDINATOR

The client designates Mr. Zahid Ul Hassan, Deputy Director, SECP Head Office NICL Building, 63 Jinnah Avenue, Islamabad as Client's Coordinator; Coordinator will provide general administration of the Contract and will be the Client representative during construction and until issuance of the final Certificate for Payment. The Coordinator shall at all times have access to the Work wherever it is in preparation and progress. The Coordinator will make periodic visits to the site to determine in general if the Work is proceeding in accordance with the Contract Documents. On the basis of on-site observations, the Coordinator will keep the record of the progress of the Work. The Coordinator will not be responsible for construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the Work, and will not be responsible for the Contractor's failure to carry out the Work in accordance with the Contract Documents. Based on such observations and the Contractor's Applications for Payment, the Coordinator will determine the amounts owing to the Contractor and will issue Certificates for Payment in accordance with Article 12. The Coordinator will be, in the first instance, the interpreter of the requirements of the Contract Documents. For payment of the invoices, approval/verification of the coordinator shall be necessary and no payment shall be made in the absence of such approval/verification as

mentioned in Article 4 of this Contract. The Coordinator will have the authority to reject Work not conforming to the Contract Documents.

ARTICLE 14 – ACCEPTANCE OF THE WORK:

The Contractor shall correct any Work that fails to conform to the requirements of the Contract Documents where such failure to conform appears during the progress of the Work, and shall remedy any defects due to faulty materials, equipment or workmanship which appear within a period of one year from the Date of Final Settlement of the Contract or within such longer period of time as may be prescribed by law or by the terms of any applicable special guarantee required by the Contract Documents. The provisions of this Article apply to Work done by Subcontractors as well as to Work done by direct employees of the Contractor, and are in addition to any other remedies or warranties provided by law. No act of the Client or the Coordinator, either in superintending or directing the Work, or any extension of time for the completion of the Work, shall be regarded as an acceptance of such Work or any part thereof, or of materials used therein, either wholly or in part. Acceptance shall be evidenced only by the final certificate of the Client or Coordinator in this behalf. Before any final certificate shall issue, Contractor shall execute an affidavit on the certificate that it accepts the same in full payment and settlement of all claims on account of Work done and materials furnished under this Contract, and that all claims for materials provided or labor performed have been paid or set aside in full. No waiver of any breach of this Contract by the Client or anyone acting on Clients' behalf shall be held as a waiver of any other subsequent breach thereof. Contractor agrees to guarantee all work under this Contract for a period of one year from the date of Final Settlement by the Client. If any unsatisfactory condition or damage develops within the time of this guaranty due to materials or workmanship that are defective, inferior, or not in accordance with the Contract, as reasonably determined by the Client or the Coordinator, then the Contractor shall, when notified by the Client or Coordinator in this behalf, immediately place such guaranteed Work in a condition satisfactory to the Client.

ARTICLE 15 - SPECIAL/MISCELLANEOUS PROVISIONS:

- a) Each Party hereto agrees to cooperate in all reasonable respects necessary to consummate the transactions contemplated by this Contract, and from time to time to do such acts and things and execute and deliver such documents and instruments as may reasonably be required in order to implement the transactions contemplated hereby. Each Party hereto agrees to cooperate in the execution of subsequent Addenda, or to re-execute an amended version of this Agreement, in the event that a Party discovers: 1) a clerical error; or 2) a misinterpretation of the law; or 3) an error as to form; when such error(s) obviate or hinder the consideration, performance, or enforcement of this Agreement.
- b) This contract is governed by the laws of the State of Pakistan and any action to enforce any of the provisions, obligations or covenants of this contract shall be commenced only in a court of proper jurisdiction in Pakistan.
- c) Contractor shall not assign this contract. The provisions of the contract are binding on the heirs, successors or assignees of the parties.

- d) The rights and remedies available under this contract shall be in addition to any rights and remedies allowed by law.
- e) No failure to enforce any provision of the contract on account of any breach thereof shall be considered as a waiver of any right to enforce provisions of this contract concerning any subsequent or continuing breach.
- f) If any provision of this Agreement is declared by any court of competent jurisdiction to be invalid for any reason, such invalidity shall not affect the remaining provisions. On the contrary, such remaining provisions shall be fully severable, and this Agreement shall be construed and enforced as if such invalid provisions never had been inserted in this Agreement.

ARTICLE 16 – STAMP DUTY

This Agreement shall be stamped in accordance with Stamp Act, 1899 by the Consultant.

ARTICLE 17 – Insurance

The Consultant will be responsible for taking out any appropriate insurance coverage.

ARTICLE 18 – Changes in the work

The client without invalidating the contract may order changes in the work consisting of any additions, deletions or modifications. All such changes in the work shall be authorized by written change order signed by the Project Coordinator. The contract sum and contract time can only be changed by Change Order signed by the Coordinator. The cost or credit to the client, if any, from a change in the work shall be determined by unit prices if specified in the contract documents or by mutual agreement.

In witness hereof the Parties have executed this Agreement on the date abovementioned.

From SECP:			
Name:			
Signature:			
From Contractor:			
Name:			
Signature:			

CECE

WITNESS (SECP side)	WITNESS (Contractor side)	
1)	1)	
2)	2)	

Format of Affidavit/Undertaking (DULY NOTARIZED)

Bidder must submit following undertaking (on stamp paper of Rs.100)) duly notarized, failing which the bid shall be rejected

a)	I, Mr
b)	That M/sis not engaged, under investigation or offences or no proceedings are pending before FBR, Customs, NAB, any Judicial form, FIA or any other Govt. authority with respect to fraud, terror financing, money laundering etc.
c)	We also confirm that our firm has not been black listed by any National/International organization or forum and its entitled to carry out its business activities to the standard business ethics.
d)	That the Partner(s) / Officers of M/s have not been subject to financial crime. Nor they every compounded with their creditors in any capacity.
e)	We, hereby agree with all the requirements and terms & conditions of the bidding document and submit the bid.
f)	The above statement is true to the best of my knowledge and belief and nothing has been concealed or is false.
	te: In case bidder is found in the list of "Blacklisted Firms-Pakistan" or related ks at https://www.ppra.org.pk/ then its bid shall be rejected
	Name:
	Signature
	Stamp:

Annex "B"

Declaration of Ultimate Beneficial Owners Information for Public Procurement Contracts.

- 1. Name
- 2. Father's Name/Spouse's Name
- 3. CNIC/NICOP/Passport No.
- 4. Nationality
- 5. Residential address
- 6. Email address
- 7. Date on which shareholding, control or interest acquired in the business.
- 8. In case of indirect shareholding, control or interest being exercised through intermediary companies, entries or other legal persons or legal arrangements in the chain of ownership or control, following additional particulars to be provided.

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.
Name	Legal form (company / Limited liability Partnership/Association of Persons/Single Member Company/partnershp Firm/Trust/Any other individual, body corporate (to be specified)	Date of Incorporation/Registra tion	Name of Registering Authority	Business Address	Country	Email Address	Percentage of Shareholding, control or interest of BO in the legal person or legal arrangement	Percentage of Shareholding, control or interest of legal person or legal arrangement in the Company	Identity of natural person who ultimately owns or controls the legal person or arrangement

9. Information about the Board of Directors (details shall be provided regarding number of shares in the capital of the company as set opposite respective names).

1.	2.	3.	4.	5.	6.	7.	8.
Name and	CNIC No.(in	Father's/Husband 's Name in	Current	Any other		Residential address in full or the	Name of shares
Surname (in	case of	Full	Nationality	Nationality(ies)	u	registered/prin cipal office addres	taken by cash
Block Letters	foreigner,				Occupatio 1	for a sunscribers other than	subscribe(in figures
	Passport No.				0	natural person	and words)
			Total numbers of sha	ares taken (in figur	es and wor	rds)	

Any other information incidental to or relevant to Beneficial Owner(s)

INTERIOR RENOVATION OF CRO OFFICE RECEPTION AREA AT FIRST FLOOR, STATE LIFE BUILDING BLUE AREA ISLAMABAD

BILL OF QUANTITIES

				K۲	

INTERIOR				Is .	
S No	Description	Qty	Unit	Rate	Amount
1	Dismantling existing works including removal of debris from site and its disposal as required by law and away from the site. Contractor to follow safety measures and SOP's while dismantling hand over all salvageable items to Owner's representative for further disposal., complete in all respect or throw out outside office premises and cda premises as per advise of the client				
a.	Dismantling of Existing ceiling any type and any height. as directed by consultant.				
b.	Dismantling of existing floor any type, as directed by consultant.	1	Job		
C.	Removing of any type of Doors with due care to not break, as directed by consultant.				
d.	Removal of wooden partitions, kitchen cabinetary, with due care to not break, as directed by consultant.				
e.	Removal of airconditioners with due care to avoid gas leakage, as directed by consultant.				
f.	Removal of electrical conduits, switch sockets, lights etc. from site with accessories, as directed by consultant.				
2	MDF BOARD PARTITION (3" Thick):- Providing and fixing of MDF wall 1.1/2"×1.1/2" at 2' c/c vertically and horizontally wood frame, clad with 1/2" thick imported malaysian MDF sheet on both side. inner gaps to be filled with mineral wool insulation, complete with cutting holes and installing back boxes, conduits, water supply pipes and other services, with all hardware accessories, and compound filling of joints with fabric tape complete in all respect, and specification or as directed by the Engineer-in-charge.	700	Sft		
2-a	MDF BOARD Cladding: Providing and fixing of MDF wall 1.1/2"×1.1/2" at 2' c/c vertically and horizontally wood frame, clad with 1/2" thick imported malaysian MDF sheet single side. inner gaps to be filled with mineral wool insulation, complete with cutting holes and installing back boxes, conduits, water supply pipes and other services, with all hardware accessories, and compound filling of joints with fabric tape complete in all respect, and specification or as directed by the Engineer-in-charge.	130	Sft		
3	WOODEN DROP BEAMS:- Providing & fixing in position wooden Beams for support to fix glass, glass door & on top of walls up to roof slab consisting of 1 1/2 x2" @ 2'-0" c/c partal wood framing fixed to walls and top on slab and 10mm thick MDF Lasani board (Malaysia) on both sides including nails, bolts, glue wastage, wood preservative, treatment & 3 coats of paint complete in all respect as per drawings and as directed by Architect.	215	Nos		
4	WOODEN RAFTERS (3" Thick):- Providing and fixing of wooden rafters in ceiling of size (3" x 6"x1'6") made in ash wood veneer fixiing it with the gypsum board ceiling including polish finish, complete with all hardware used., as per drawing, complete in all respect.	6	Nos		
5	GYPSUM BOARD FALSE CEILING:- Providing and fixing of Gypsum Board false ceiling, at least 1/2" thick of imported Elephant Brand or equivelant brand, with Metal suspension system consisting of galvanized steel channel, intermediated channel, splices, hangers, hanger adjustment clips with fabric tape on edge as per design, light fittings as per consultants instructions including making holes and to assist in fixing, as per drawing, complete in all respect. and specification or as directed by Consultant.	1400	Sft		

6	Laminated Gypsum Tile Ceiling Providing and fixing 600 x 600mm single sides laminated gypsum board false ceiling,including wastage of materials (make DFB or equivalent) with aluminum foil at back side with imported aluminum powder coated of approved suspension system (CKM ceiling suspension system UT/FUT series) with Disco T, as per drawing and design complete in all respects. FEATURE WALL (WPC PANELIING):- Providing & fixing of Wood plastic Composit (WPC)wall palelling in Fluted patterned on to existing masonry wall with proper aluminum clapping system, including with all surface preparation ,complete	450 100	Sft Sft	
8	with all hardware used as per design. MDF STRIPS CLADDING: Providing & fixing MDF strips cllding on wall in deco paint finish on to MDF partation wall, including with all surface preparation, complete with all hardware used as per design.	20	Sft	
9	WOODEN CLADDING WITH POLISH FINISH:- Providing & fixing of Column and drope beam cladding made of 2"x2" acacia wood frame with 3/4" thick imported ASH wood ply cladding on side, including polish finish with all surface preparation ,complete with all hardware used as per design.	75	Sft	
10	WOODEN PELMET WITH CORIAN FINISH:- Providing and fixing of wood pelmet made of 1/2" MDF sheet cladding with 12mm thick corian with 2"x2" wooden frame 6"ft drop from ceiling above the planter and connicting it with the reception counter as per consultants, complete in all respect.	60	Sft	
11	RECEPTION COUNTERS:- Providing and Fixing Reception Counter in Radial shape, 4" thick top two levels with 24" & 12" vide, made up of 3/4" thick lamination board cladding with 12mm thick Corian fixed on top and 3/4" thick MDF strips caldding fixed on front panel in Deco Paint finish, with approved colour specification, including drawer unit and all hardware used, as per manufactures specification complete in all respect as per drawings or as directed by architect, As Shown in picture.	50	Sft	
12	Providing & laying imported Porcelain tiles of 2'x2' make of TIME caremics or MASTER or Equivalent make in approved color and shade laid with dry bond including jointing with Quartz Lock Grout of approved color, including Leveling, washing and curing. complete in all respect. Market Tile Base Rate Rs. 2500/- Sqm Excl GST	1200	Sft	
13	PORCELAIN TILE TOILET:- Providing & laying imported Porcelain tiles of size 1' x 3' for toilet floor and walls make TIME caremics or MASTER or Equivalent in approved color and shade laid with dry bond including jointing with Quartz Lock Grout of approved color, including Leveling, washing and curing. complete in all respect. Market Tile Base Rate Rs. 2500/- Sqm Excl GST.	1000	Sft	
14	Wooden Floor Providing and laying of imported wooden floor With Insloation as			
15	per Designs etc. 12mm GLASS PARTATION	300	Sft	
a	Providing and fixing of 12mm thick glass partition with frosted sheet of approved design, 1-1/2" aluminum concealed 'U' channel, complete in all respect as per drawings and as approved by the Consultant.	190	Sft	

Ь	12mm GLASS DOORS :-		П	
─ ─	Providing and fixing, 12 mm thick tempered glass door including SS		1 . 1	
c.	door handle 4' height, patch fitting, locks with imported best quality	30	Sft	
	floor machine complete in all respects.			
	FROSTING FILM:			
d	Provide and installation of frosting film of make 3M on glass as per	200	Sft	
	design, complete in all respects.			
16	KITCHEN CABINETS:-			
	Provide and install 24" deep and 32" height cabinets made up of 3/4			
	" thick white MDF lamination used for box, & ¾ " thick Al-noor			
	Tactile series sheets with edges for shutter, with marble top base	200	Sft	
a	price 600 Rs along with Kitchen Concealed hinges, magnetic			
	catchers, locks, SS handles complete with all hardware used as per			
	drawing ,complete in all respect.			
	Provide and install 15" deep and 24" height cabinets made up of ¾			
	" thick white MDF lamination used for box, & ¾ " thick Al-noor			
b	Tactile series sheets with mechine edges for shutter, with Kitchen	25	Sft	
	Concealed hinges, magnetic catchers, locks, SS handles complete			
	with all hardware used as per drawing ,complete in all respect.			
	SKIRTING:-			
17	Provide and fixing tile skirting 4" height same as floor tile using dry	500	Rft	
1/	bond including jointing with Quartz Lock Grout of approved color all	500	KIL	
	hardware used complete in all respect.			
	EMULSION PAINT :-			
18	Providing and applying plastic emulsion of approved shade three	6000	Sft	
	coats over a primer coat and required coats of Putty Filling to make			
	smooth surface as using ICI or equivalent. BASE FLOOR PLASTER:-		-	
	Providing and laying ¾ " thick 1:4 cement sand plaster under floor,			
19	including chipping, leveling, curing etc. with steel finish complete in	1800	Sft	
13	all respect as per drawings or as directed by the engineer in charge.	1000	310	
	(excluding back filling and pcc)			
	PLANTER BOX WITH PLANTS:-			
20	Providing ,suppling and febrecating planter box made of MDF with	15	Sft	
20	tile cladding same as floor with white marbel chips filling around	15		
	the open space along with assorted indoor plants		1	
	STONE CLADDING :-			
21	Providing & fixing of random stone strips cladding on MDF	62	C ft	
21	partition wall with imported silicone adhesive , including with all	62	Sft	
	surface preparation ,complete with all hardware used as per design.			
	Wooden Door		 	
	Providing, fabricating and installing in position single or Double leaf			
33	Ash Ply on both sides Solid flush door shutters 1-1/2" thick design	FO	Ctr	
22	built up from first quality ash wood lipping on both sides with 1/8"	50	Sft	
	th. Ash wood plywood veneer ,1-1/4"x4" Dewedar wood fram and			
	filled with partal wood . Complete with all beads. Architraves.			
	Mirror 5mm Sam Guard			
	Providing of fixing of 5mm thick looking glass (Imported Sam Guard) first quality 66" x 36" size, with crystal bevelled edges			
23		12	Sft	
	mounted fixed to the wall, SS screws and washers complete in all			
	respects.			
	FREE STANDING SCREENS			
	Providing and fixing of free standing creens using 10 mm MDF			
24	sheets with laser cut rendom pattrens with spot colours along with	90	Sft	
24	s.s clamps connecting with s.s pipes from top and bottom with all	30	ا اا	
	hardware accessories complete in all respect, and specification or			
	as directed by the Engineer-in-charge.			
	Total			-

Electrical Works

S. No.	Description	Qty	Unit	Rate	Amount
1	CIRCUIT POINT WIRING				

а	Supply and wiring of light circuit from DB to switchboard / Presence Detector (PD) with 2x2.5mmsq single core insulated 300/500 volt grade cables(P+N) and 2.5mmsq cable as protective conductor (PC) in & including PVC conduit installed/ recessed in walls / R.C.C. Slab, on ceiling or as required as per site conditions. Complete with all conduit accessories junction boxes, pull boxes as required complete in all respects as per specifications and drawings.	6	Each	
b	Supply and wiring of first light point consisting of one point controlled by one switch with 2x1.5mmsq (P+N) PVC insulated 300/500 volt grade wire in and including PVC conduits recessed in walls/R.C.C. slab, on ceilings or as required including all conduit accessories junction boxes, pull boxes, pull wire, 2.5mm2 cable as CPC complete with 10 Amp. single way switch make as approved by consultant (annexure-A) installed on & including 16 SWG sheet steel boards duly powder coated paint with earth bolt recessed in wall/column complete in all respects as per drawing & specifications.	14	Each	
С	Same as item No. 2.03 above but point to point wiring.	80	Each	
d	Supply and wiring of multi pin 5/10 Amps socket outlet from DB to socket with single core 2x2.5mmsq PVC insulated 300/500 volt grade cable in & including PVC conduit recessed in walls/R.C.C. slab, or on surface of ceiling including all conduits accessories, junction boxes, pull boxes etc including 16 SWG sheet steel box recessed in walls, complete in all respect.	8	Each	
e	Supply and wiring of multi pin 5/10 Amps socket outlet point to point with single core 2x1.5mmsq PVC insulated 300/500 volt grade cable in & including PVC conduit recessed in walls/R.C.C. slab, or on surface of ceiling including all conduits accessories, junction boxes, pull boxes etc. & including 16 SWG sheet steel board recessed in walls complete in all respects and as per specifications & drawings.	24	Each	
f	Supply and Wiring of one 15A power sockets outlet with 2x 4mmsq single core cables (P+N) and 2.5 mmsq as CPC from DB to point including cost of one Nos. 15A 3 pin switch socket outlet make Schynider as approved by consultant installed on & including 16 SWG sheet steel boards recessed in walls /columns, Complete in all respects.	4	Each	
2	FITTING FIXTURES AND FANS			
а	Providing ,installation ,testing and commissioning of the following lighting fixture including all accessories like electronic ballast, drivery circuitry , lamps, mountings etc. Complete in all respects.			
b	Down lighter covered with glass with 1x12 Watt SMD having color temperature ranging from 2700K to 4500K, lumen efficacy of 80 lm/Watt (Lumen/Watt) and operational power factor of 0.9 complete in all respects.	85	Each	

d	Supply & Installation of self contained Non maintained "EXIT LIGHT" No. CFS-EXT 300 make Alco/ Honeywell Esser or approved by the consultant with Fluorescent lamp NICAD batteries for 3 hours back up.	1	Each	
е	Supply & Installation of dual head "Emergency Light" No. CFS-EMG 300 battery operated (2xHLD Lamp) make Alco / Honeywell or approved by the consultant.	2	Each	
f	Supply and installation of rope light complete in all respects.	100	Rft	
g	Supply and installation of Ceiling suspended hanging light with 1x12/15 Watt LED Lamp installed complete hanging arrangement, complete in all respects.	2	Each	
3	VOICE & DATA			
a	Supply & Laying of 1" dia PVC pipe to be laid under floor or wall or ceiling including floor cutting as required, laying of CAT 6 cable of make Schynider or 3M including 16 SWG back box and face plate and I/Os of make Schynider and its termination at both ends for Voice as per design along with Fluke testing of all nodes complete in all respects	8	Nos	
С	Supply, Installation & connecting of 4 pair STP CAT-6 cable from each networking switch to main server rack as secondary backbone to be drawn in given prelaid PVC pipe complete in all respects with Fluke testing of all nodes complete in all respects.	150	Rft	
d	Providing and Installation of patch panel 24 port of make Cisco or Juniper and its termination including installation of wall mounted IT rack.	1	Nos	
d-1	Providing and Installation of Network cabinet of adequate size to adjust existing as well as the new installation of network points	1	Nos	
е	Supply and installation of Patch Cord , to be installed on specified location as per advised by architect / engineer's incharge:-			
i)	Cat-6 Patch Cord (1 Mtr)	12	Nos	
ii)	Cat-6 Patch Cord (3 Mtr)	10	Nos	
4 а	FIRE ALARM SYSTEM (CONVENTIONAL) Supply, installation and connecting of non-addressable manual call stations press glass type and its connection with existing system.	1	Each	
b	Supply, installation and connecting of non-addressable optical smoke detectors, complete in all respects and conforming to general specifications.	2	Each	
5	CC TV SYSTEM (IP BASED)			
а	Wiring for each IP Based POE CCTV Cameras to be installed	3	Each	
6	on walls / slabs or on false ceiling with cable CAT 6 UTP Cable WI-FI NETWORKING SYSTEM			
a	Wiring for each POE Wi-Fi Access points to be installed on walls / slabs or on false ceiling with cable CAT-6 UTP Cable cable in 1" dia PVC conduit (excluding cost of pipe) make Plasco / Beta Pipes, complete in all respects.	3	Each	
7	QUE MANAGEMENT / SELF SERVICE KISOK SYSTEM			
а	Queue Management system existing Shifting	1	Job	

d	Supply at site, installation testing & commissioning of Feed back devices compatible with the existing system make Qnet as approved by electrical consultant, complete in all respects.	Nos	
8	Distribution Boards:		
a	Commissioning with existing Distribution Boards including cost of additional breakers and DB box as per site requirement.	No	
	Total Cost of Electrical Works		

	HVAC Works				
S. No.	Description	Qty	Unit	Rate	Amount
1	HVAC Works				
1-a	SINGLE SPLIT (INVERTER TYPE) AIR CONDITIONING SYSTEM, Supply & Installation of heat Pump (Heat & Cool inverter type) DX Split Type Air Conditioning Units, As Specified & Scheduled including unloading, Lifting, Placing and Fixing at foundations as shown on the drawings make Gree/Haier/equivalent				
2-a	Wall Mounted Unite				
2-b	WMU-B (Net Cap: 1.5 Tons)	1	Nos		
2-c	Supply and installation of Copper piping for 1.5 tons using 3/8 & 5/8 copper piping with insulation airconditioners as per design.	300	Rft		
_	Total Cost of HVAC Works	_			

	Sanitory Work:				
S. No.	Description	Qty	Unit	Rate	Amount
	FIXTURES / ACCESSORIES				-
1	Providing and installing Water Closet English type Porta (Code: HD-101N) with close coupled cistern, Master make chromium plated stop cock, plastic seat, lid etc. including all fittings required to complete the installation.	3	No		
2	Providing and installing Water Closet Indian type Porta (Code: HD-70) with close coupled cistern, Master make chromium plated stop cock, plastic seat, lid etc. including all fittings required to complete the installation.	1	No		
3	Providing and installing Wash Hand Basin porta Wall Hung type (Code: HDLP-311) , Master make chromium plated stop cocks, UPVC waste pipe etc.including all fitting required to complete ithe installation.				
	a) Wall Hung Type	3	No		
4	Providing and installing S.S 24" Bowl Sink Super Asia make Under counter Master make chromium plated stop cocks, UPVC waste pipe etc.including all fitting required to complete ithe installation.	1	No		
5	Providing and installing Master make Mixers including all fittings required to complete the installation.				
	a) Single lever Sing Mixture Porta	1	No		
6	Providing and installing approved quality 1/2" dia Porta make chrome plated double Bib Cock with Muslim Shower and C P Nozel.	4	No		
	Providing and installing approved quality 1/2" dia make Porta T Cock With C P Nozel	14	Nos		
7	Providing and installing of SS Soap Dispenser best quality complete with installation	3	No		

8	Providing and fixing SS toilet Paper Holder Porta .	4	No	
9	Providing and fixing SS Towel Rail Porta of approved quality complete with C.P brackets & screws.	3	No	
	Providing and fixing looking glass 5mm thick, with hardboard backing and fixing on wall with SS bolts complete as per design and as directed by the client.		Sft	
11	Electric Geyser Ariston: Providing, installing and fixing of Electric geyser ariston, complete in all respect	1	Nos	
12	U - PVC Pipe: Providing and laying best quality of 4" dia U-PVC pipe Popular brand, Master Fit for soil, waste and vent lines including all accessories 4" thick PCC 1:4:8 bedding under pipe (by using crushed stone) complete with excavation back-filling whereever required, making of holes etc. complete in all respects.	6	Nos	
13	Water Supply pipes: Providing and laying best quality popular brand, Master PPRC pipes for cold and hot water supply lines including all imported specials fitting, including cutting and jointing materials, hooks, making grooves in walls and filling the same with 1:4 cement sand mortar, excavation and back filling where required including for concealed pipes and testing up to required pressure complete in all respects. (Quantity will be take on actual measurement.) 25mm and 32mm dia pipe with complete fitting	4	Nos	
	Total Plumbing Works			

	Furniture					
S. No.	Description	Pictures	Qty	Unit	Rate	Amount
1	CHAIRS FOR FACILITATION COUNTER					
1	HIGH BACK REVOLVING CHAIR					
а	Providing and supplying revolving chair with cushioned Seat and Back, frame as per manufacturer's specs, approved color and sample, Having 5-star revolving adjustable threaded pedestal, durable & load bearing castor wheels. complete as per manufactures specification or as directed by architect, As Shown in picture.		3			
b	STOOL CHAIR Providing & supplying with cushioned seat fitted in SS frame and base height adjustment mechanism sizes as per manufacturer's specifications complete per Picture or as directed by architect.		4			
2	Work stations					
	Provide and supplying Self service Counters 3'-6" high made up of 30"x18" x 3" thick top shelve with corain coating, 3"x3" MS powder coated hollow pipe support connected with base with 1/4" powder coated ms plate, 18"x9"x24" Tile clad wood box for CPU and other accessories complete as picture and manufacturer's specifications.		4			
3	SOFA CHAIRS	W-1				

	Provide and supplying Single sofa inleatherette top with master molty foam and sain lees steel legs as per the reference image and manufacturer's specifications.		11		
4	GLASS TOP TABLES	1			
а	Provide and supplying Center table with 12mm thick glass top with stainlees steel legs as per the reference image and manufacturer's specifications.	Contract of the Contract of th	1		
b	Provide and supplying coffe table with 12mm thick glass top with stainlees steel legs as per the reference image and manufacturer's specifications.	The second second	1		
	METAL RACK				
С	Providing & supplying Shelving rack made up of powder coated MS 1" pipe frame with laminated shelves, PVC Edge lipping, approved color, and shape, as per picture and Quality as per manufactures. specification or as directed by site incharge		30		
	Total Furniture:				

S No	R WORKS: Description	Qty	Unit	Rate	Amount
1	Dismantling existing works including removal of debris from site and its disposal as required by law and away from the site. Contractor to follow safety measures and SOP's while dismantling hand over all salvageable items to Owner's representative for further disposal., complete in all respect.	4.7	0,		7,110
b.	Dismantling of existing floor any type, as directed by consultant.				
C.	Removing of any type of Doors with due care to not break, as directed by consultant.	1	Job		
d.	Removal of wooden and Glass partitions, with due care to not break, as directed by consultant.				
e.	Removal of airconditioners with due care to avoid gas leakage, as directed by consultant.				
f.	Removal of electrical conduits, switch sockets, lights etc. from site with accessories, as directed by consultant.				
2	MDF BOARD PARTITION (3" Thick):- Providing and fixing of full heigh MDF partation 1.1/2"×1.1/2" at 2' c/c vertically and horizontally wood frame, clad with 1/2" thick imported malaysian MDF sheet on both side., complete with cutting holes and installing back boxes, conduits, water supply pipes and other services, with all hardware accessories, and compound filling of joints with fabric tape complete in all respect, and specification or as directed by the Engineer-in-charge.	200	Sft		
	MDF BOARD Cladding :-				
2	Providing and fixing of MDF wall 1.1/2"×1.1/2" at 2' c/c vertically and horizontally wood frame, clad with 1/2" thick imported malaysian MDF sheet single side. inner gaps to be filled with mineral wool insulation, complete with cutting holes and installing back boxes, conduits, water supply pipes and other services, with all hardware accessories, and compound filling of joints with fabric tape complete in all respect, and specification or as directed by the Engineer-in-charge.	56	Sft		
	MDF LOW HEIGHT BOARD PARTITION (3" Thick) :-				
3	Providing and fixing o f4'-0" heigh MDF partation 1.1/2"×1.1/2" at 2' c/c vertically and horizontally wood frame, clad with 1/2" thick imported malaysian MDF sheet on both side., complete with cutting holes and installing back boxes, conduits, water supply pipes and other services, with all hardware accessories, and compound filling of joints with fabric tape complete in all respect, and specification or as directed by the Engineer-in-charge.	151	Sft		

4	Laminated Gypsum Tile Ceiling Providing and fixing 600 x 600mm single sides laminated gypsum board false ceiling,including wastage of materials (make DFB or equivalent) with aluminum foil at back side with imported aluminum powder coated of approved suspension system (CKM ceiling suspension system UT/FUT series) with Disco T, as per drawing and design complete in all respects.		Sft	
5	PORCELAIN TILE FLOOR:- Providing & laying imported Porcelain tiles of size 2' x 4' aur 2'x2' make of times, master or equal company make in approved color and shade laid with dry bond including jointing with Quartz Lock Grout of approved color, including Leveling, washing and curing. complete in all respect. Market Tile Base Rate Rs. 3,000/- Sqm Excl GST	2200	Sft	
6	SKIRTING:- Provide and fixing tile skirting 4" height same as floor tile using dry bond including jointing with Quartz Lock Grout of approved color all hardware used complete in all respect.	450	Rft	
7	EMULSION PAINT:- Providing and applying plastic emulsion of approved shade three coats over a primer coat and required coats of Putty Filling to make smooth surface as using ICI or equivalent.	3500	Sft	
8	Provide and fix in position roller blinds , Make in selected colour and shade, includes all screws, rawal plugs etc. required for fixing and accessories, complete in all respects as per drawings and design or directed by the consultant.		Sft	-
9	BASE FLOOR PLASTER:- Providing and laying ¾ " thick 1:4 cement sand plaster under floor, including chipping, leveling, curing etc. with steel finish complete in all respect as per drawings or as directed by the engineer In charge. (excluding back filling and pcc)	1635	Sft	

ELECTRICAL

S No	Description	Qty	Unit	Rate	Amount
1	CIRCUIT POINT WIRING				
а	Supply and wiring of light circuit from DB to switchboard / Presence Detector (PD) with 2x2.5mmsq single core insulated 300/500 volt grade cables(P+N) and 2.5mmsq cable as protective conductor (PC) in & including PVC conduit installed/ recessed in walls / R.C.C. Slab, on ceiling or as required as per site conditions. Complete with all conduit accessories junction boxes, pull boxes as required complete in all respects as per specifications and drawings.	4	Each		
b	Supply and wiring of first light point consisting of one point controlled by one switch with 2x1.5mmsq (P+N) PVC insulated 300/500 volt grade wire in and including PVC conduits recessed in walls/R.C.C. slab, on ceilings or as required including all conduit accessories junction boxes, pull boxes, pull wire, 2.5mm2 cable as CPC complete with 10 Amp. single way switch make as approved by consultant (annexure-A) installed on & including 16 SWG sheet steel boards duly powder coated paint with earth bolt recessed in wall/column complete in all respects as per drawing & specifications.	4	Each		
С	Same as item No. 2.03 above but point to point wiring.	16	Each		

d	Supply and wiring of multi pin 5/10 Amps socket outlet from DB to socket with single core 2x2.5mmsq PVC insulated 300/500 volt grade cable in & including PVC conduit recessed in walls/R.C.C. slab, or on surface of ceiling including all conduits accessories, junction boxes, pull boxes etc including 16 SWG sheet steel box recessed in walls, complete in all respect.	4	Each	
е	Supply and wiring of multi pin 5/10 Amps socket outlet point to point with single core 2x1.5mmsq PVC insulated 300/500 volt grade cable in & including PVC conduit recessed in walls/R.C.C. slab, or on surface of ceiling including all conduits accessories, junction boxes, pull boxes etc. & including 16 SWG sheet steel board recessed in walls complete in all respects and as per specifications & drawings.	5	Each	
2	FITTING FIXTURES AND FANS			
a	Providing installation testing and commissioning of the following lighting fixture including all accessories like electronic ballast, drivery circuitry, lamps, mountings etc. Complete in all respects.			
b	Down lighter covered with glass with 1x12 Watt SMD having color temperature ranging from 2700K to 4500K, lumen efficacy of 80 lm/Watt (Lumen/Watt) and operational power factor of 0.9 complete in all respects.		Each	
	Total			-

SUMMARY OF COST:

S No	Description	Amount - PKR
1	Civil / Hard Interior Works	
2	Electrical Works	
3	HVAC Works	
4	PLUMBING Works	
5	Furniture	
6	Support staff Area	
7	Support staff Furniture	
	Total Amount	

Note:- Contractor to submit Shop drawings for approval of the Architect before fabrication). The rates include cost of all sampling and Mockups as desired by the Architect. All work shall be finished as per entire satisfaction of Owner/Architect with proper tools and practices while making good any damage to existing surface or equipment. Contractor to follow SOP's for COVID as per Govt Directions.

MARCH 2024



SECURITIES AND EXCHANGE COMMISSION OF PAKISTAN

(SECP)

COMPANY REGISTRATION OFFICE

(RENOVATION OF RECEPTION AREA 1st FLOOR)

TENDER DRAWING SET (INTERIOR, ELECTRICAL & HVAC)



CONSULTANT:

FORESENIC DESIGN

Office # 14-D, REHMAT PLAZA, BLUE AREA , ISLAMABAD-Pakistan

Tel: +92-51-2275425, Fax: +92-51-2271297

Web Site: www.foresenicdesign.com E-Mail: info@foresenicdesign.com

LIST OF DRAWINGS

S/NO	DRG/NO	DESCRIPTION		S/NO	DRG/NO	DESCRIPTION		S/NO	DRW/NO	DESCRIPTION
01	A-100	LIST OF DRAWING **DELECTRICAL DRAWINGS** **HVAC DRAWINGS** **HVAC DRAWINGS** **DELECTRICAL DRAWINGS** **HVAC DRAWINGS** **HVAC DRAWINGS** **DELECTRICAL DRAWINGS** **DELECTRICAL DRAWINGS** **DELECTRICAL DRAWINGS** **HVAC DRAWINGS** **DELECTRICAL DRAWINGS** **HVAC DRAWINGS** **DELECTRICAL DR				HVAC DRAWINGS				
		INTERIOR DRAWINGS		23	E-101	LEGENDS. (ELECTRICAL)	✓	45	H-101	HVAC LAYOUT PLAN
02	A-101	AS BUILT LAYOUT PLAN	✓	24	E-102	GENERAL NOTES (ELECTRICAL)	\checkmark	46	H-102	TYPICAL OUTDOOR UNIT DETAIL
03	A-102	PROPOSED FURNITURE LAYOUT PLAN	✓	25	E-103	GENERAL NOTES (ELECTRICAL)	\checkmark	47		
04	A-103	DISMANTLING LAYOUT PLAN	✓	26	E-104	LIGHT LAYOUT PLAN	\checkmark	48		
05	A-104	WORKING PLAN	✓	27	E-105	POWER ,VOICE & DATA LAYOUT PLAN	✓	49		
06	A-105	GLASS PARTITION DETAIL	✓	28				50		
07	A-106	RECEPTION COUNTER DETAIL	✓	29						
08	A-106-a	RECEPTION COUNTER DETAIL (SECTION)	✓	30						
09	A-107	WAITING AREA WALL CLADDING DETAIL	✓	31						
10	A-108	LOW HEIGHT PARTITION DETAIL	✓	32						
11	A-109	WORKSTATION DETAIL	✓	33						
12	A-110	KITCHEN COUNTER DETAIL	✓	34						
13	A-111	PARTITION DETAIL WITH CNC PATTERN	✓	35						
14	A-112	FLOORING WORKING PLAN	✓	36						
15	A-113	FALSE CEILING WORKING PLAN AND SECTION	✓	37						
16	A-114	TYPICAL WOODEN DOOR DETAIL	✓	38						
17	A-115	3D VIEWS	✓	39						
18	A-116	3D VIEWS	✓	40						
19				41						
20				42						
21				43						
22				44						



GENERAL NOTES:

- THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS, CONDITIONS OF CONTRACT ETC
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
А		
В		
С		
D		
E		
F		
G		
н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT :



UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

FORESENIC DESIGNS

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

SECP (DIRECTOR GENERAL OF TRADE ORGANIZATION)

Project Status: TENDER DRAWINGS

(RECEPTION AREA)

LIST OF DRAWING

Designed:	Che	cked:
Muhammad Ibrahim Khan	Mu	hammad Ibrahim Khan
Drawn:	Scal	e:
Mubasher Nazir		N.T.S
Project Number:		Rev:
ID - 0130)	0

Drawing Number:

SECURITIES AND EXCHANGE COMMISSION OF PAKISTAN

(SECP)

TENDER DRAWING SET

(INTERIOR)





CONSULTANT:


FORESENIC DESIGN


Office # 14-D, REHMAT PLAZA, BLUE AREA, ISLAMABAD-Pakistan Tel: +92-51-2275425,


Fax: +92-51-2271297 Web Site: www.foresenicdesign.com E-Mail: info@foresenicdesign.com



















- THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
A		
В		
С		
D		
E		
F		
G		
Н		
J		
К	·	
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT :



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:


(DIRECTOR GENERAL OF TRADE ORGANIZATION)


Project Status:

TENDER DRAWINGS (RECEPTION AREA)


GLASS PARTITION DETAIL

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 013	0 0
Drawing Number:	





ELEVATION - 02









Client

GENERAL NOTES:

- 1. THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS, CONDITIONS OF CONTRACT ETC
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
А		
В		
С		
D		
E		
F		
G		
Н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT:



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

SECP
(DIRECTOR GENERAL OF TRADE ORGANIZATION)

Project Status:


TENDER DRAWINGS (RECEPTION AREA)

Drawlng:

RECEPTION COUNTER DETAIL

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0

Drawing Number:





- 1. THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
A		
В		
С		
D		
E		
F		
G		
н		
J		
К	<u> </u>	
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT :



FORESENIC

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

(DIRECTOR GENERAL OF TRADE ORGANIZATION)


Project Status:


TENDER DRAWINGS (RECEPTION AREA)


RECEPTION COUNTER DETAIL (SECTION)

ID - 0130	0
Project Number	Rev:
Mubasher Nazir	N.T.S
Drawn:	Scale:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Designed:	Checked:

A - 106-a









- THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH
- 6, CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
A		
В		
С		
D		
E		
F		
G		
Н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT :



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:


SECP (DIRECTOR GENERAL OF TRADE ORGANIZATION)

Project Status


TENDER DRAWINGS (RECEPTION AREA)

WAITING AREA WALL CLADDING DETAIL

Designed:		Checked:	
Muhammad Ibrahim Khan		hammad Ibrahim Khan	
Drawn:	Scale:		
Mubasher Nazir		N.T.S	
Project Number:		Rev:	
ID - 0130)	0	
Drawing Number:			
A - 107			



ELEVATION - 01





Clie

GENERAL NOTES:

- THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS, CONDITIONS OF CONTRACT FTC
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
A		
В		
С		
D		
E		
F		
G		
Н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT :



DESIGNS

FORESENIC

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD. PH: 051 2275425, Mob: 0300 9505228. Email:info@foresericdesign.com

Project:

SECP
(DIRECTOR GENERAL OF TRADE ORGANIZATION)


Project Status:

TENDER DRAWINGS (RECEPTION AREA)

Drawing:

LOW HEIGHT PARTITION DETAIL

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Kha
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0 0
Drawing Number:	





STRUCTURAL CONSULTANT

CONSTRUCTION WORK

3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING

4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC

5. THIS DRAWING TO BE READ IN CONJUNCTION WITH

7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.

Description

Date

ARCHITECT : Designs

FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

(DIRECTOR GENERAL OF TRADE ORGANIZATION)


Project Status:

TENDER DRAWINGS (RECEPTION AREA)


WORKSTATION DETAIL


Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0
Drawing Number:	


A - 109




WORKSTATION







ELEVATION - 01





- 1. THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS
- 2. ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER

Rev	Description	Date
А		
В		
С		
D		
E		
F		
G		
н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT



FORESENIC DESIGNS

UNIT # 14-D FIRST FLOOR REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:


SECP (DIRECTOR GENERAL OF TRADE ORGANIZATION)


roject Status TENDER DRAWINGS


PARTITION DETAIL WITH CNC PATTERN

(RECEPTION AREA)

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0
Drawing Number:	1









NOTE:

NO./SIZE	D (3'-0" x 7'-0")
TYPE	SINGLE LEAF HINGED
DESCRIPTION	FRAME: SOLID DEODAR WOOD FRAME LEAF: FLASH DOOR FINISH: OAK WOOD PLY CLADDING
HARDWARE	S.S DOOR HANDLE AND LOCK SET,S.S HINGE.



Client

GENERAL NOTES:

- THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS, CONDITIONS OF CONTRACT ETC
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
А		
В		
С		
D		
E		
F		
G		
Н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT:



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

SECP

(DIRECTOR GENERAL OF TRADE ORGANIZATION)
Project Status:

(RECEPTION AREA)

TENDER DRAWINGS

Drowlnau

TYPICAL WOODEN DOOR DETAIL

ID - 0130	0
Project Number:	Rev:
Mubasher Nazir	N.T.S
Drawn:	Scale:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Designed:	Checked:











- 1. THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS, CONDITIONS OF CONTRACT ETC
- 6, CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
А		
В		
С		
D		
E		
F		
G		
Н		
J		
К		
M		

STRUCTURAL CONSULTANT

ARCHITECT :



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:


SECP

(DIRECTOR GENERAL OF TRADE ORGANIZATION) roject Status:

TENDER DRAWINGS (RECEPTION AREA)

3D VIEWS

ID - 0130	0
Project Number:	Rev:
Mubasher Nazir	N.T.S
Drawn:	Scale:
Muhammad Ibrahim Khan	Muhammad Ibrahim Kha
Designed:	Checked:











Client

GENERAL NOTES:

- 1. THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS, CONDITIONS OF CONTRACT ETC
- 6, CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Date

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT:



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

SECP

(DIRECTOR GENERAL OF TRADE ORGANIZATION)
Project Status:

TENDER DRAWINGS (RECEPTION AREA)

Drawlng:

3D VIEWS

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khar
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0
Drawing Number:	

SECURITIES AND EXCHANGE COMMISSION OF PAKISTAN

(SECP)

TENDER DRAWING SET

(ELECTRICAL)



CONSULTANT:

FORESENIC DESIGN

Office # 14-D, REHMAT PLAZA, BLUE AREA, ISLAMABAD-Pakistan Tel: +92-51-2275425,

Fax: +92-51-2271297

Web Site: www.foresenicdesign.com E-Mail: info@foresenicdesign.com

LEGEND

SYMBOL	DESCRIPTION
	FLUORESCENT TUBE LIGHT, 1X36W, WITH PFIC PHILIPS CAT. No. TMS-140 OR SUNLIGHTING MODL No. DELTA-140 MOUNTED ON CEILING / WALL
	WALL LIGHTING FIXTURE, AS APPROVED BY CONSULTANT MOUNTED ON CEILING / WALL 7'-0" ABOVE FROM FINISHED FLOOR LEVEL
⊢	WALL LIGHTING FIXTURE , ON MIRROR IN BATH MOUNTED ON CEILING / WALL JUST ABOVE MIRROR
\bigotimes	WALL LIGHTING FIXTURE WITH WIRE GUARD (WEATHER PROOF BULK HEAD TYPE), IP 65, WITH 26 WATTS PLCE/CFL ENERGY SAVER LAMP AND AS APPROVED SUN LIGHTING MODEL No. OD 7009 MOUNTED ON WALL, 7'-0" ABOVE FROM FINISHED FLOOR LEVEL
0	CEILING LIGHTING FIXTURE , IN BATH MOUNTED ON CEILING
1	
	HANGING LIGHT FROM CEILING
	CONCELEAD 2'X2' CEILING FAN MADE OF MANUFACTURER AS MENTIONED IN LIST OF APPROVED MANUFACTURERS HANGING FROM CEILING
10" DIA €	EXHAUST FAN ,OF MENTIONED DIA AND SIMILAR MOUNTED ON WALL 8'-0" ABOVE FROM FINISHED FLOOR LEVEL
	DUEL SOCKET DATA & VOICE. 2x3 PIN FLAT (UK) PORTS (DUEL SOCKET) FOR UPS POWER CONNECTION. 1x2 PIN ROUND (FRENCH) POWER CONNECTION FOR WAPDAH.
\odot	MOUNTED ON WALL PUSH BUTTON FOR ABOVE DOOR BELL 4'-0" ABOVE FROM FINISHED FLOOR LEVEL
68	SWITCH 1-WAY, 5 AMP, 6 IN NUMBER AND SIMILAR MOUNTED ON WALL 4'-0" ABOVE FROM FINISHED FLOOR LEVEL
1S2	SWITCH 2-WAY, 5 AMP, ONE IN NUMBER AND SIMILAR MOUNTED ON WALL 4'-0" ABOVE FROM FINISHED FLOOR LEVEL
_	DATA SOCKET
	SWITCH SOCKET 5 A, 220 V, 3/5 PIN, MOUNTED ON WALL/PARTITION 9" ABOVE FROM FINISHED FLOOR LEVEL
	SHAVER SOCKET , AS PER BS 3052 MOUNTED ON WALL ASIDE BATH MIRROR
	SWITCH SOCKET 15 A, 220 V, 3 PIN, MOUNTED ON WALL/PATITION 9" ABOVE FROM FINISHED FLOOR LEVEL
√ 1S	SWITCH 1-WAY, 10 AMP, ONE IN NUMBER AND SIMILAR MOUNTED ON WALL 4'-0" ABOVE FROM FINISHED FLOOR LEVEL

LEGEND			
SYMBOL	DESCRIPTION		
	CASSETTE TYPE AC		
AC	SWITCH SOCKET 20 / 25 A, 220 V, 3 PIN, FOR AC MOUNTED ON WALL 5'-6" ABOVE FROM FINISHED FLOOR LEVEL		
DB-F1	DISTRIBUTION BOARD-F1 AND SIMILAR MOUNTED ON WALL TOP OF DB TO BE 6'-0" ABOVE FROM FINISHED FLOOR LEVEL		
<u>\</u>	mcb (MINIATURE CIRCUIT BREAKER) , 10 A , SP , AND SIMILAR INSTALLED IN DB		
30 A, 6 KA minimum	MCCB(MOULDED CASE CIRCUIT BREAKER) , 30 A , TP , OF MINIMUM 6KA OR NEXT HIGHER RUPTURING CAPACITY AND SIMILAR, INSTALLED IN DB		
	TELE PHONE EXCHANGE		
۵	CABLE TV POINT MOUNTED ON WALL/PARTITION, 9" ABOVE FROM FINISHED FLOOR LEVEL		
Δ	TELEPHONE POINT MOUNTED ON WALL/ PARTITION, 9" ABOVE FROM FINISHED FLOOR LEVEL		
TYPE - A	EARTH POINT (ELECTRODE) , TYPE - A		
☐ ECP	EARTH CONNECTING POINT		
DB-G/R1	CONDUIT GOING DIRECTLY TO DB-G AND WIRES CONNECTION WITH CIRCUIT NO. RI AND SIMILAR		
M	ELECTRIC METER (KWH ENERGY METER) TO BE INSTALLED BY ELECTRIC SUPPLY COMPANY		
• UP	CONDUIT GOING / TURNING UP		
• DN	CONDUIT GOING / TURNING DOWN		
• UP/DN	CONDUIT COMING FROM UP AND GOING DOWN WITHOUT HAVING ANY JUNCTION OR PULL BOX		
SP	SINGLE POLE / SINGLE PHASE		
DP	DOUBLE POLE		
TP	TRIPLE POLE / THREE PHASE		
FP	FOUR POLE		
MCCB	MOULDED CASE CIRCUIT BREKER		
ELCB	EARTH LEAKAGE CIRCUIT BREAKER		
MCB / mcb	MINIATURE CIRCUIT BREKER		
CPC	CIRCUIT PROTECTIVE CONDUCTOR (EARTH WIRE)		
300 mA	300 MILLI AMPS SENSITIVITY OF EARTH LEAKAGE CIRCUIT BREAKER AND SIMILAR		
JB	JUNCTION BOX MOUNTED ON WALL, 1'-0" ABOVE FROM FINISHED FLOOR LEVEL		
TJB	TELEPHONE JUNCTION BOX MOUNTED ON WALL, 1'-0" ABOVE FROM FINISHED FLOOR LEVEL		
TVJB	CABLE TV JUNCTION BOX MOUNTED ON WALL, 1'-0" ABOVE FROM FINISHED FLOOR LEVEL		
STANDING AC	STANDING AC		



Client

GENERAL NOTES:

- THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS, CONDITIONS OF CONTRACT ETC
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
A		
В		
С		
D		
E		
F		
G		
н		
J	·	
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT:



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

SECP
(DIRECTOR GENERAL OF TRADE ORGANIZATION)

Status:

Project Status:

TENDER DRAWINGS (RECEPTION AREA)

Drawlng:

LEGENDS ELECTRICAL

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0

Drawing Number:

E - 101

NOTES:

- 1- THE WHOLE OF THE ELECTRIC WORK SHALL BE CARRIED OUT ONLY BE THE LICENCED CONTRACTOR, AUTHORISED BY THE

 GOVERNMENT TO UNDERTAKE SUCH WORK, UNDER THE PROVISION OF THE PAKISTAN ELECTRICITY RULES AND UNDER THE

 DIRECT SUPERVISION OF WHOLE TIME ELECTRICAL SUPERVISOR, HAVING REQUIRED CERTIFICATE OF COMPETENCY, FOR THE TYPE

 OF WORK UNDER EXECUTION.
- 2- THE WHOLE OF ELECTRIC WORK SHALL BE CARRIED OUT IN STRICT ACCORDANCE WITH THE REGULATIONS OF THE ELECTRIC

 EQUIPMENT OF BUILDINGS (LATEST EDITION) AS ISSUED BY THE INSTITUTE OF ELECTRICAL ENGINEERS LONDON AND SHALL ALSO

 COMPLY WITH PROVISIONS OF THE PAKISTAN ELECTRICITY RULES.
- 3- READ ALL OF THE ELECTRICAL DRAWING CAREFULLY AND IN 100 % BEFORE STARTING THE WORK AT SITE (FOR PROPOSES OF NOTINGS FOR SHOP DRAWINGS AND FOR CO-ORDINATION WITH OTHER SERVICES etc.).
- 4- THE CONDUIT SHALL BE LAID IN CEILING SLAB OF THAT FLOOR UNLESS OTHERWISE NOOTED
- 5- PROVIDE CONCEALED JUNCTION/PULL BOXES WHEN EVER MORE THAN TWO NINETY DEGREE BENDS/TURNS ARE MADE IN A CONDUIT RUN.

 A PULL BOX SHALL ALSO BE PROVIDED FOR EVERY 75 FEET OF STRAIGHT CONDUIT RUN.
- 6- AVOID JUNCTION/PULL BOXES WHEN EVER NOT REQUIRED AS THESE DO NOT APPEAR GOOD ARCHITECTURLY.
- 7- THE WIRING THROUGH CONDUIT SHALL BE STARTED ONLY AFTER CONDUITING SYSTEM IS COMPLETELY INSTALLED AND ALL OUT LET
 BOXES, JUNCTION BOXES etc. ARE FIXED IN POSITION.
- 8- THE WIRES SHALL BE PULLED IN THE CONDUIT WITH CARE AND, TO FACILITATE PULLING, THE MANUFACTURER'S RECOMMENDED LUBRICANT
 SHALL BE USED. USE OF ANY KIND OF OIL OR SOAP WILL NOT BE PERMITTED.
- 9- WHERE SEVERAL WIRES ARE TO BE RUN IN THE SAME CONDUIT, THOSE SHALL BE PULLED IN TOGETHER.
- 10- THE WIRES SHALL NOT BE BENT TO A RADIUS LESS THAN 10 TIMES THEIR OVER ALL DIAMETER OF THE WIRES, UNLESS OTHERWISE RECOMMENDED BY THE MANUFACTURER.
- 11- THE WIRING SHALL BE CONTINUOUS BETWEEN TERMINATIONS.
- 12- THE LOOPING-IN SYSTEM SHALL BE FOLLOWED THROUGH OUT. ANY JOINT IN WIRES WILL NOT BE ALLOWED. THE USE OF CONNECTORS WILL ONLY BE ALLOWED AT LOCATIONS WHERE LOOPING-IN IS RENDERED DIFFICULT. THE CONSENT OF THE ENGINEER-INCHARGE, IN WRITING, WILL BE REQUIRED FOR USING CONNECTORS.
- 13- ALL CONDUIT SHALL BE CONCEALED AND OF PVC FOR GENERAL USE.
- 14- PVC CONDUIT SHALL BE MADE OF M/S PAKISTAN PVC LTD. KARACHI AND NAME " SHAVYL ".
- 15- MIN. SIZE OF CONDUIT IS 3/4 " DIA.
- 16- WIRES/CABLES SHALL BE MADE OF M/S PAKISTAN CABLES LTD. KARACHI AND OF COPPER CONDUCTOR ONLY.
- 17- ALL CONDUIT FOR TELEPHONE SYSTEM IS 1" DIA UNLESS OTHERWISE NOTED.

NOTES:

- 18- CIRCUIT BREAKERS ARE MADE OF M/S MERLIN GERIN FRANCE.
- 19- PROVIDE A PULL WIRE OF 12 INCHES OF SLACK AT EACH END OF THE CONDUIT RUN
- 20- THE DISTANCE OF THE SWITCH BOX FROM WHERE THE DOOR STARTS WILL BE 8" OR AS APPROVED BY ENGINEER-INCHARGE.
- 21- FACE PLATES OF SWITCH, SOCKETS, TELEPHONE AND OTHER OUTLETS SHALL BE FLUSH WITH FINISHED SURFACE.
- 22- THE ELECTRICAL RESISTANCE OF ECC TOGETHER WITH EARTH LEAD AND EARTH ELECTRODE SHALL NOT EXCEED 1 OHM.
 - IF THE RESISTANCE TO EARTH EXCEEDS TO 1 OHM, THEN CONTRACTOR SHALL OBTAIN INSTRUCTIONS FROM THE CONSULTANT FOR ANY RECTIFICATION. RUN TWO SEPERATE LEADS TO EACH ELECTRODE.
- 23- CIRCUIT DIRECTORY SHALL BE MARKED ON DBs AS PER DRAWING.
- 24- ALL CIRCUIT BREAKERS ARE OF 6 KA INTERRUPTING CAPACITY, UNLESS OTHERWISE NOTED.
- 25- WHEN EVER MORE POWER ONE CIRCUIT (SINGLE PHASE FOR LIGHT AND SOCKETS etc.) RUN IN ONE COMMON CONDUIT, EACH CIRUIT

 SHALL HAVE ITS OWN SEPERATE AND INDEPENDENT PHASE WIRE, NEUTRAL WIRE AND ECC. NEUTRAL WIRE SHALL HAVE THE SIZE

 EQUAL TO ITS PHASE WIRE. NEUTRAL WIRE AND ECC OF ONE CIRCUIT SHALL NOT BE MADE COMMON WITH NEUTRAL WIRE AND ECC.
- 26- USE SEPERATE SWITCH BOX FOR EACH CIRCUIT IF THERE ARE MORE. THAN ONE CIRCUIT COMMING AT ONE LOCATION.
- 27- THE MOUNTING HEIGHT OF DIFFERENT FIXTURES ABOVE FINISHED FLOOR LEVEL SHALL BE AS FOLLOWIING AS MEASURED FROM THE BOTTOM OF FIXTURE.
 - a. DISTRIBUTION BOARD - - 3'-6".
 - b. LIGHT AND FAN CONTROL SWITCH - - 3'-6".
 - c. 5 A, 15 A/20 A SWITCH SOCKETS - - 1'-0".
 - d. 15/20 A SWITCH SOCKET FOR A/C - AT LEVEL AS PER A/C MOUNTING POSITION.
 - e. WALL MOUNTING LIGHT. LIGHT BRACKETS - - 7'-0".
- 28- USE FLEXIBLE CONDUIT WHEREVER OTHER CONDUITS CROSS EXPANSION JOINT TO AVOID BREAKAGE OF CONDUITS AND WIRES.
- 29- ALL OF THE CONDUIT (FOR ALL SORT OF SOCKETS, TEL, TV etc.) WILL BE LAID IN CEILING SLAB OF THAT FLOOR.
- 30- ALL CONDUIT FOR TV AND FIRE ALARM SYSTEMS ARE 1" DIA, UNLESS OTHERWISE NOTED.
- 31- FOR EACH SPLIT A/C UNITS, POWER CIRCUIT IS SHOWN NEAR INDOOR UNIT
 - THE WIRING / CONDUITING BETWEEN ITS INDOOR UNIT (EVAPORATOR) AND OUTDOOR UNIT (CONDENSOR) WILL BE DONE BY OTHERS (A/C CONTRACTOR).
- 32- SWITCHES ON EMERGENCY GENERATOR SUPPLY WILL HAVE SEPARATE SWITCH BACK BOXES.
- 33- SUFFIX " E " STANDS FOR "POINTS ON EMERGENCY GENERATOR SUPPLY".
- 34- FOR TELEPHONE AND TV SYSTEMS, ONLY CONDUIT WITH DRAW WIRE AND RESPECTIVE SOCKET WILL BE
 - PROVIDED BY BUILDING CONTRACTOR UNDER THIS CONTRACT.
 - THE WIRES WILL BE PULLED-IN BY OTHER CONTRACTOR / VENDOR UNDER SEPARATE CONTRACT.



Client

GENERAL NOTES:

- 1. THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH
- SPECIFICATIONS, CONDITIONS OF CONTRACT ETC
 CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE
- STRUCTURAL, MEP ETC DRAWINGS

 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- LARGER SCALE DRAWING WILL SUPERSEDE SMALLER
 SCALE DRAWING.

Rev	Description	Date
A		
В		
С		
D		
E		
F		
G		
Н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

SECP
(DIRECTOR GENERAL OF TRADE ORGANIZATION)

ect Status:

Project Status

TENDER DRAWINGS (reception area)

Drawlng:

Drawing Number:


GENERAL NOTES ELECTRICAL

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0

E - 102

EARTHING ELECTRODE DETAIL (TYPE-B)-HARDEN<u>ED STEEL</u> DRIVING STUD 1450x450 —HEAVY DUTY C.I COVER _15mm M.S. ANGLE SEE DETAIL' 13mm dia TO EARTH CONNECTING—POINT COPPER EARTHING ROD 50mm DIA G.I. PIPE DOWEL 1:4:8 CC BASE 🛱 STONE SOLING COPPER ELECTRODE EARTH FILLING SOIL/EARTH HARDENED STEEL 13mm Ø COPPER ROD 3000 LONG IN THREE PARTS SCREWED TOGETHER SCALE: NTS NOTE: ALL DIMENSIONS ARE IN mm.

EARTH POINT DETAIL



SCHEDULE OF WIRES FOR WIRING (WIRES WILL BE OF 450/750 VOLTS GRADE)

LICE OF WIDEC	SIZE OF WIRES		
USE OF WIRES	PHASE	NEUTRAL	ECC / CPC
CIRCUIT WIRES FOR LIGHT, FAN, 5 A SOCKET	2.5 sq. mm	2.5 sq. mm	2.5 sq. mm
POINTS WIRING WIRES FOR LIGHT, FAN, 5 A SOCKET	1.5 sq. mm	1.5 sq. mm	1.5 sq. mm
15/20 A SOCKET FOR GENERAL USE	4 sq. mm	4 sq. mm	4 sq. mm
WIRING FOR A/C FROM DB TO FCU TO CU	6 sq. mm	6 sq. mm	6 sq. mm

MAXIMUM CAPACITY OF PVC CONDUIT

WIRE CONDUCTOR SIZE	SIZE OF PVC CONDUITS		
	20 mm (3/4")	25 mm (1")	32 mm (1 1/4")
1.5 sq. mm	8	18	26
2.5 sq. mm	6	11	17
4 sq. mm	4	8	13
6 sq. mm	3	6	10

List of Approved Manufacturers and Suppliers

S. No.	MATERIAL	APPROVED MANUFACTURERS
1.	PVC Conduits and Accessories	a) M/S BETA PIPES , LAHORE b) M/S PAKISTAN PVC Ltd. , TRADE NAME "SHAVYL" c) M/S GALAXY , TRADE NAME "GALCO"
2.	WIRES / CABLES / HDBCC	a) M/S PAKISTAN CABLES Ltd., KARACHI b) M/S NEWAGE CABLES Ltd., LAHORE c) M/S PIONEER CABLES d) M/S FAST CABLES
3.	SWITCHES / SOCKETS / TV OUTLET AND ACCESSORIES etc.	a) M/S CLIPSAL , AUSTRALIA b) M/S TENBY , ENGLAND c) M/S EDISON , UK
4.	LIGHTING FIXTURES	a) M/S PHILIPS PAKISTAN b) M/S SUN LIGHTING PAKISTAN c) M/S CLIPSAL, AUSTRALIA
5.	LAMPS AND BALLASTS / CHOKES etc.	a) M/S PHILIPS PAKISTAN b) M/S SUN LIGHTING PAKISTAN c) M/S CLIPSAL, AUSTRALIA
6.	FANS	a) M/S MILLAT b) M/S ASIA c) PAK FANS
7.	LT CIRCUIT BREAKERS (Equipment Only)	a) G. E. AMERICA and its subsideriesb) M. G. (MERLIN GERIN) FRANCEc) SIEMENS (Pak) Engg. Co.
8.	LT PANELS AND DISTRIBUTION BOARDS (Manufacturing Only)	a) SIEMENS (Pak) Engg. Co. b) IMAM TRADING, RATTA PLAZA, BLUE AREA , ISLAMABAD c) ELECTRICH, LAHORE d) JAMIL ELECTRIC , LAHORE
9.	CONTACTOR/ RELAYS (Equipment Only)	a) NATIONAL b) TELEMECANIQUE, FRANCE
10.	BACK BOXES / PULL BOXES / JUNCTION BOXES /	a) IMAM TRADING, RATTA PLAZA, BLUE AREA , ISLAMABAD b) M/S EDISON , UK c) M/S HUSAIN & Co., Karachi
11.	EMERGENCY DIESEL GENERATOR SET	a) CATER PILLAR, USA b) AS APPROVED



Client

GENERAL NOTES:

- 1. THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
A		
В		
С		
D		
E		
F		
G		
н		
J		
К		
М		
MED CONSULTANT		

STRUCTURAL CONSULTANT

ARCHITECT :



UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project: SECP

(DIRECTOR GENERAL OF TRADE ORGANIZATION)

Project Status: TENDER DRAWINGS

(RECEPTION AREA)


Drawlng:


GENERAL NOTES ELECTRICAL

Designed:	Checked:	
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan	
Drawn:	Scale:	
Mubasher Nazir	N.T.S	
Project Number:	Rev:	
ID - 0130	0	

Drawing Number:

E - 103





SECURITIES AND EXCHANGE COMMISSION OF PAKISTAN

(SECP)

TENDER DRAWING SET

(HVAC)




CONSULTANT:


FORESENIC DESIGN

Office # 14-D, REHMAT PLAZA, BLUE AREA, ISLAMABAD-Pakistan Tel: +92-51-2275425,

Tel: +92-51-2275425, Fax: +92-51-2271297 Web Site: www.foresenicd

Web Site: www.foresenicdesign.com E-Mail: info@foresenicdesign.com






CEILING CASSETTE TYPE SPLIT AIR CONDITION							
UNIT REFFERENCE		TOTAL COOLING CAPACITY	OTAL COOLING CAPACITY POWER SUPPLY		ELECTRIC POWER	REMARKS	
ONII KEITEKENCE	QTY	BTU/H	VOLTS	PH	HZ	KW	REMARKS
MEZZANINE FLOOR							
AC-CC # A- 01	3 Nob	18,000	230	1	50	2.68	

NOTE:

THE SELECTION OF AIR CONDITIONING UNIT SHALL BE MADE ON 45 DEGREE CENTIGRADE CONDENSER AIR ENTERING TEMPERATURE





Clie

GENERAL NOTES:

- THIS DRAWING IS NOT TO BE SCALED, STATED DIMENSIONS
 ARE ONLY TO BE CONSIDERED
- ALL DIMENSIONS ARE TO BE VERIFIED ON SITE AS PER
 ACTUAL SITE CONDITION PRIOR TO COMMENCEMENT OF ANY
 CONSTRUCTION WORK
- 3. ANY DISCREPANCIES IN DIMENSIONS & OR INFORMATION SHOULD BE BROUGHT TO THE ATTENTION OF THE CONSULTANT IN WRITING
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH STRUCTURAL AND MEP DRAWINGS ETC
- 5. THIS DRAWING TO BE READ IN CONJUNCTION WITH
- 6. CONTRACTOR SHOULD CO-ORDINATE ALL WORKS WITH THE STRUCTURAL, MEP ETC DRAWINGS
- 7. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF FORESENIC DESIGN.
- 8. LARGER SCALE DRAWING WILL SUPERSEDE SMALLER SCALE DRAWING.

Rev	Description	Date
А		
В		
С		
D		
E		
F		
G		
Н		
J		
К		
М		

MEP CONSULTANT

STRUCTURAL CONSULTANT

ARCHITECT :



FORESENIC DESIGNS

UNIT # 14-D,FIRST FLOOR, REHMAT PLAZA, BLUE AREA, ISLAMABAD.

PH: 051 2275425, Mob: 0300 9505228. Email:info@foresenicdesign.com

Project:

SECP
(DIRECTOR GENERAL OF TRADE ORGANIZATION)

Project Status:

TENDER DRAWINGS

Drawing:

TYPICAL OUTDOOR UNIT DETAIL

(RECEPTION AREA)

Designed:	Checked:
Muhammad Ibrahim Khan	Muhammad Ibrahim Khan
Drawn:	Scale:
Mubasher Nazir	N.T.S
Project Number:	Rev:
ID - 0130	0
Drawing Number:	1

H - 102

SPECIFICATIONS

SECTION - 8001

GENERAL SPECIFICATIONS FOR ELECTRICAL WORKS

1.0 SCOPE OF WORK

The works related to the electrical system are included in the Scope of this Contract as shown on the Drawings, stated in the Specifications and Bill of Quantities and explained in these Specifications. The works shall broadly include but not limited to the following:

- General Specifications for Electrical Works
- LT Distribution Boards
- Light Fixtures
- Low Tension Cables
- Wiring Accessories
- Conduits and Pipes
- Earthing
- Miscellaneous Items
- Structured Cabling Network
- Intelligent Addressable Fire Alarm System
- Closed Circuit Television System
- Cable Antenna TV System

The Contractor shall also be responsible to supply any other equipment not specifically mentioned in these Documents but which is necessary for proper operation of the works/system included in the scope of this Contract. The Contractor shall solely be responsible for ensuring proper functional requirements of different equipment. He shall also be responsible for furnishing any additional piece of equipment and for making modification in the equipment as desired and/or approved by the Engineer to achieve proper co-ordination with various equipment offered in the bid and also with those installed by others.

2.0 RULES & REGULATIONS

The entire electrical installation/work shall be carried out by licensed Contractor, authorised to undertake such work under the provisions of the Electricity Act 1910 and The Electricity Rules 1937 as adopted and modified upto date by the Government of Pakistan.

All works shall be carried out in accordance with the latest edition of the Regulations of the Electrical Equipment of Buildings issued by the Institute of Electrical Engineers-London, the Contract Documents, The Electricity Rules 1937 and bye-laws that are in force from time to time. Any discrepancy between these Specifications and any other rules and regulations shall be brought to the notice of Engineer for his instructions and the discussion of the accepting/controlling shall be final and conclusive.

The Contractor shall be responsible for completing all formalities and submitting the test certificates as per prevailing rules and regulations, and shall have the installation passed by the Government Electric Inspector of that region. All requirements of the Electric Inspector and the KE (Karachi Electric) shall be complied with.

3.0 **AMBIENT CONDITIONS**

All material and equipment supplied and installed shall be designed, manufactured and tested to meet the following ambient conditions unless specifically stated otherwise for any material/equipment.

Location Lahore

Maximum indoors ambient temperature 50-Degree Celsius Minimum indoors ambient temperature Zero Degrees Celsius 50-Degree Celsius Maximum outdoors-ambient temperature Zero Degrees Celsius Minimum outdoors-ambient temperature

Maximum Relative humidity 100 Percent

Maximum Altitude of project 520 meters above the mean sea level.

The atmospheric conditions are tropical and highly humid.

4.0 **STANDARDS**

The latest standards and codes of reputable organisations shall be applicable for the material and equipment specified herein and for installation work. Such organisations to be BSS, IEC, VDE, NFPA 99, NEC Article 517 etc. In case the Specifications laid down herein differ from those given in the standards, then the equivalent or better specifications shall govern. Wherever applicable the equipment shall also conform to the requirements of Pakistan Standard Institution (PSI).

Contractor shall maintain at the site office one copy of the standards / codes applicable to the works.

5.0 SYSTEM DATA

Unless otherwise specified elsewhere, all equipment and material shall be designed to operate satisfactorily with the following minimum requirements without any de-rating.

a) Voltage rating of equipment: HT: 11 kV, 3 phase, +/- 10%

LT: 415 V, 3 phase, +/- 10% 240 V, 1 phase, +/- 10%

b) Frequency : 50Hz + 2Hz

In general, the electrical colour coding of switchgear cubicles, control panels, desks etc., shall be in accordance with the respective IEC Recommendations. Live parts of electrical connections shall be colour coded according to IEC 446 as follows:

Conductor Designation	Coding Alphanumeric	Colour
A.C. Network Phase 1	L 1	red
Phase 2	L 2	yellow
Phase 3	L 3	blue

	Neutral	N	black
D.C. Network	Positive Negative	L+ L-	white black
Earthing	Protective Earth Earth	PE E	green/yellow green/yellow

The colour coding for the secondary circuits of isolated power panel board is as follows:

Orange-Isolated Phase Conductor Brown- Isolated Neutral Conductor Green-Isolated Ground Conductor

Conductor insulation of secondary circuits of isolated power panel board shall be XLPE and PVC sheathed.

Control Cables

The Control Cables shall be manufactured according to specifications for L.T. Cables. The Control Cables shall be of multi-core, PVC insulated type withstanding without deterioration the conditions prevailing at the place of installation. The cross section of cable shall be as per the requirement of the system.

All the cores should be numbered and/or colour coded or otherwise properly identified. At-least 20% spare cores shall be provided in all Control Cables.

No separate payment is admissible for supplying, installing, testing and commissioning of control cables and is deemed to have been included in the BOQ rates of the respective equipment.

Distance in between power, communication and control cables shall be kept as per requirements laid down by EN50174-2, NEC800 and NFPA 70.

6.0 **EQUIPMENT**

6.1 IP Degree of Protection

The equipment shall have IP degree of protection as follows, unless mentioned other wise:

- IP 42 for indoor areas
- IP 54 for indoor damp areas
- IP 65 for outdoor areas

If properly rated equipment is not available, the Contractor shall provide field enclosures to attain the required IP degree of protection. If necessary cooling/exhaust fans and / or anti condensate heaters shall also be provided. No separate payment shall be made to attain the required IP degree of protection.

6.2 Identification & Labelling

All devices, meters, cabling, wiring and auxiliaries shall be properly labeled for identification. Labeling of equipment shall be done by means of flameproof material using indelible ink/marking. The labeling shall be such as to ensure uniformity and shall facilitate study of control diagrams/ drawings during operation and maintenance.

All labeling shall be of suitable size to be visible from the operating conditions/positions at site.

6.3 Lamp Test Facility

All equipment / switchboards, etc. shall be provided with common lamp test facility.

7.0 DRAWINGS AND DATA TO BE FURNISHED BY THE CONTRACTOR

For each electrical equipment shop drawings, as-built drawings and/or technical data are to be furnished by the Contractor. LT cable distribution layouts & shall include, but not limited to the following:

- (a) Structural drawings showing foundations, RCC details dimensional plans, elevation and sections on a suitable scale.
- (b) Electrical drawings showing:
 - Line diagrams of Switchboards, Motor Control Centres, distribution boards and isolated power panels with detailed wiring diagrams, elevations/internal component layout and other standard details.
 - LT Cabling, Grounding/Earthing including all cable routing and support details.
 - Necessary execution details such as no. of cable/wires, size of conduits, cable routes, cable trays and cable trenches, etc.
 - Substation and Generator Room Equipment installation details.
 - Manhole/Duct works.
- (c) Layouts of all LT cable routes with coordinates and levels.
- (d) Technical literature and manufacturer's characteristic data with the description of materials and weights of all equipment as instructed by the Engineer.

At least three (3) copies of the shop drawings and/or technical data of the equipment shall be submitted to the Engineer for checking and approval.

8.0 MANUFACTURER'S INSTRUCTIONS

The Contractor shall supply to the Engineer in properly bound form six (6) copies of manufacturer's instruction manuals for installation, testing, commissioning, operation and maintenance of the specified equipment including manuals of spare parts and tools of the equipment. At least two copies of the documents shall be submitted in original. The installation instructions shall be submitted 2

weeks prior to commencement of installation of each equipment, and operation and maintenance instruction at the time of commissioning. If the Contractor fails to provide the documents the Engineer shall withhold issuance of requisite certificates and deduct suitable amount from the payments to the Contractor.

9.0 **GUARANTEE**

The Contractor shall furnish written guarantee of the manufacturer or supplier with respect to satisfactory performance of each equipment. Guarantee shall be given for replacement and repair of part or whole of the equipment, which may be found defective in material or workmanship. The guarantee shall cover the duration of Maintenance Period as defined in the Conditions of Contract. This guarantee shall not relieve the Contractor of his obligations and he will be fully responsible for the repair or replacement of any defective material in time, so as not to cause any undue delay in carrying out the repairs and/or replacements.

10.0 DANGER BOARDS WITH SIGNS, DESIGNATION AND SHOCK / FIRST AID CHARTS AND FIRE FIGHTING EQUIPMENT

Danger Boards having signs and designation of the room shall be installed on the external door of HT, LT, Power transformer, Low Voltage DG Set Rooms. Shock/First Aid Charts shall be installed in H.T, L.T and Low Voltage DG Set Rooms.

Potable fire fighting extinguisher suitable to control electrical fire shall be provided in H.T, L.T, Power Transformer and Low Voltage DG Set Rooms.

All the above items shall also be provided, wherever required to comply the requirements of the Pakistan Electricity Rules/Electric Inspector.

Laminated single line and adequate detail drawings on proper boards highlighting the main system features shall be displayed/ fixed in respective electrical and communication rooms.

11.0 ASSOCIATED CIVIL WORKS

Except where separately stated in the Bill of Quantities the cost of all civil works associated with any BOQ item of electrical works, such as excavation and back filling of earth, compaction of the earth, foundation pads, chiselling, making openings, etc. shall be included in the price quoted against respective items. No separate payment for such works will be made. Such works will also include repair of any damage to civil works caused by the Contractor during electrical installation.

12.0 INSTALLATION INSTRUCTIONS - GENERAL

The Contractor shall furnish all labour, materials, tools and equipment required to install, connect, test and commission all electrical equipment specified herein, whether or not such equipment is furnished by him or by others.

For all equipment to be installed by the Contractor, the Contractor shall supply and install all erection materials such as foundation bolts, washers, nuts, etc. as required and without any additional costs.

The Contractor shall set out the works himself as per Specifications and Drawings and shall properly position the equipment on specified

foundation/location. In general, the manufacturer's instructions for installation shall be followed. Any defect or faulty operation of equipment due to the Contractor not following the manufacturer's instructions shall be corrected and repaired by the Contractor at his own cost.

For any deviation from the working drawings or specification that are deemed necessary by the Contractor due to site conditions, he shall submit the details and obtain the Engineer approval before starting such works.

13.0 FACTORY TESTS

All type and routine tests on Low Voltage D.G Set, Power Transformer, H.T Switchboards, LT Switchboards, Motor Control Centre, H.T Cables, LT Cables, and all other equipment shall be performed at the manufacturer's works in the presence of the Engineer or his Representative. Type tests may be waived off in case test certificates are submitted as certified by an Engineer approved standard laboratory of international repute; but merely producing the test type certificates will not relieve the manufacturer to carry out the required standard/routine tests.

The Contractor shall inform the Engineer about the date and time of test of each equipment at least two weeks in advance. This shall, however, be done after the Contractor has got the test procedures duly approved by the Engineer. The witnessing of test by the Engineer and the Employer shall not absolve the Contractor from his responsibility for the proper functioning of the equipment, and for furnishing the guarantees referred to in clause 9.0. All test results shall be supplied in quadruplicate. All expenses for carrying out the tests as incurred by the Engineer and the Employer to witness it shall be borne by the Contractor and deemed to have been included in the bid. Provision for at least two person's visit for Factory Acceptance Tests shall be made to include one representative each from the Employer and the Consultant/Engineer. The contractor shall undertake all formalities as may be required for the Engineer or his representative to enable him make the visit.

14.0 TESTING

14.1 **Scope**

Upon completion of the installation, the Contractor shall perform field tests on all equipment, materials and systems. All tests shall be conducted in the presence of the Engineer for the purpose of demonstrating equipment or system compliance with Specifications. The Contractor shall submit for Engineer's approval complete details of tests to be performed describing the procedure, test observations and expected results.

The Contractor shall furnish all tools, instruments, test equipment, materials, etc., and all qualified personnel required for the testing, setting and adjustment of all electrical equipment and material including putting the same into operation.

All tests shall be made with proper regard for the protection of the personnel and equipment and the Contractor shall be responsible for adequate protection of all personnel and equipment during such tests. The cost of any damages or rectification work due to any accident during the tests shall be the sole responsibility of Contractor.

The Contractor shall record all test values of the tests made by him on all equipment. Four (4) copies of all test data and results certified by the Engineer shall be given to the Engineer for record purposes. These shall also include details of testing method, testing equipment, diagrams, etc.

The witnessing of any tests by the Engineer does not relieve the Contractor of his guarantees for materials, equipment and workmanship, or as any other obligations of Contract.

14.2 Low Voltage D.G. Set

Prior to the tests, the contractor shall submit manufacturer's recommended detailed description of the test procedures to be conducted for Engineer's approval.

The Contractor shall carry out full site load and no load tests in accordance with IEC, ISO or BS Specifications for site commissioning. The inspection and tests shall include but not be limited to:

Basic Tests: Insulation Resistance

Earth Continuity

Earth Loop Impedance

Polarity

Phase Rotation

Voltage and Frequency

Starting System
Protection Equipment

Battery: Nominal Voltage

Discharge Voltage

Specific Gravity of Electrolyte

Level of Electrolyte Charging System

Lubrication: Check as required by manufacturer

Operational Check at

Start-up

Oil Pressure

Fuel Oil Leaks

Operation of Safety Devices

Operational Speed Automatic Control Instrument Check Exhaust Check Undue Vibration Oil Pressure

Operational Check
After one hour's run:

Oil Leaks Cooling System Oil Temperature

Commissioning Test: 25% of full load 0.5 hrs.

50% of full load 0.5 hrs. 75% of full load 1 hrs. 110% of full load 1 hr. 110% of full load 1 hr.

All commissioning and test results shall be recorded and compared with design data. A retest/commissioning shall take place if results are not satisfactory. All the tools, labour, POL, required for the testing and commissioning shall be provided by the Contractor at no extra cost. If required load is not available at site for testing the generators, the Contractor shall provide dummy load at site at no extra cost to the Employer. The correct functioning of the control equipment shall also be proved.

Battery Charger

Battery charger shall be static type and shall provide for both trickle and boost charging of the batteries when the engine is not in operation. The charger shall be of suitable capacity to fully recharge the completely discharged batteries within four hours at boost charge.

Control Panel

The Control Panel shall provide all the necessary control and monitoring devices of the Diesel Generating Sets. All the control and monitoring of the safety devices, alarms, protections, meters, lamps, etc. as mentioned in this Specifications and required as per good engineering practices for such an installation shall be provided in the Control Panel.

14.3 Transformer Tests

In addition to the insulation resistance test of the transformer, a polarity and phase rotation test shall also be made. Buchholz relay shall be tested for proper operation. Di-electric test shall be carried out on transformer oil prior to putting the same in operation.

14.4 HT / LT Switchboards

Each circuit breaker shall be operated electrically and mechanically. All interlocks and control circuits shall be checked for proper connections in accordance with the wiring diagrams given by the manufacturer.

The Contractor shall properly identify the phases of all switchgear and cables for connections to give proper phase sequence.

Trip circuits shall be checked for correct operation and rating of equipment served. The correct size and function of fuses, disconnect switches, number of interlocks, indicating lights, alarms and remote control devices shall be in accordance with approved manufacturer drawings. Nameplates shall be checked for proper designation of equipment served. Protective relays shall be tested and set at site prior to commissioning of the equipment.

14.6 Insulation Resistance Test

Insulation resistance test shall be made on all electrical equipment by using a meggar of 500 volts for circuits upto 250 volts and 1000 volt for circuits between 250 and 500 volts. For testing of 11 kV circuits, upto 5

kV meggar shall be used; the exact voltage shall be as advised by the equipment manufacturer unless otherwise advised by the Engineer.

The insulation resistance values of cables, transformer, switchgears, etc., shall be as per BSS, IEEE, NEC, ICEA and Pakistan Electricity Rules.

Before making connections at the ends of each cable run or joint between cables, the insulation resistance test of each cable section shall be made. H.T. cables shall be subjected to high voltage test as per recommendations of standard to which the cable is manufactured. Each conductor of a multi-core cable shall be tested individually with each of the other conductor of the group and also with earth. If insulation resistance test readings are found to be less than the specified minimum in any conductor, the entire cable shall be replaced and tests repeated on new cable. If cable joint is provided, then each cable section shall be tested, and joint made only after the tests have been made satisfactorily. Finally the completed cable length including the joints shall be tested.

The transformer and switchgears shall be given an insulation resistance measurement test after installation, but before any wiring is connected. Insulation tests shall be made between open contacts of circuit breakers, switches and between each phase and earth.

If the insulation resistance of the circuit under test is less than the specified value, the cause of the low reading shall be determined and removed. Corrective measures shall include dry-out procedure by means of heaters, if equipment is found to contain moisture. Where corrective measures are carried out, the insulation resistance readings shall be taken after the correction has been made and repeated twice at 12 hours interval. The maximum range for each reading in the three successive tests shall not exceed 20% of the average value. After all tests have been made, the equipment shall be reconnected as required. Polarity test shall be made on single pole switching devices.

14.7 Earth Resistance Test

The Contractor shall make Earth resistance tests on the Earthing system, separating and reconnecting each earth connection.

If it is indicated that soil treatment or other corrective measures are required to lower the ground resistance values, the Engineer will determine the extent of such corrective measures.

The electrical resistance of the ECC together with the resistance of the Earthing leads measured from the connection with earth electrode to any other position in the complete installation shall not exceed one ohm.

Earth resistance test shall be performed as per Electrical Inspector's requirements. Where more than one earth electrodes are installed, the earth resistance test of each electrode shall be measured by means of resistance bridge instrument.

The complete lightning protection system shall be tested for continuity and earth resistance. The combined earth resistance at any point in the lightning protection system shall not exceed 10 ohms.

14.8 Completed Tests

After any equipment has been tested, checked for operation, etc., and is accepted by the Engineer the Contractor shall be responsible for the proper protection of that equipment so that subsequent testing of other equipment do not cause any damage to the already tested equipment.

14.9 Expenses

All expenses, i.e., daily allowance (as per NESPAK rules & policy), travelling, boarding and lodging for carrying out the tests and witnessing by the Engineer shall be borne by the Contractor and are deemed to have been included in the BOQ rates of the respective equipment(s) by the Contractor.

14.10 Spare Parts

Contractor shall provide necessary spare parts as per manufacturer's recommendation. The cost of each spare parts shall be carried over to relevant BOQ item and no extra payment shall be admissible in this regard.

14.11 Special Tools

Contractor shall provide special tools and instruments as may be deemed essential for assembly, adjustment, dismantling, installation and maintenance reasons. No separate payment shall be made for any special tools and instruments, and cost shall be deemed to be included in the cost of the Contract.

15.0 APPENDICES TO BE FILLED IN BY THE BIDDER

The details regarding equipment manufacturers, deviations, etc., are to be furnished in the attached form of Bids.

16.0 PAYMENT

No separate payment shall be made for work involved within the scope of this section unless specifically stated in the Bill of Quantities or herein.

*** End of Section 8001 ***

Volume-I

LIST OF APPROVED MANUFACTURERS AND BRANDS OF MATERIALS/EQUIPMENT

This list of approved manufacturer's or brands of different materials or equipments is provided in order to establish a standard level of performance and do not indicate any preference for a particular manufacture or material or brand. The Contractor is bound to provide and fix the material or equipments of superior quality approved by the Engineer from the list. However, the material provided from the list of approved manufacturer's shall meet the requirements of the BoQ, relevant specifications come under specification section 8001 of the bidding documents. The contractor shall directly procure material from factory source or the authorized dealers. The Contractor shall provide in support the delivery challan from factory or from supplier including letter of authorization for dealership, sole agent, distributor from the principal, for ensuring the quality, warranty and guarantee of purchased equipment.

SR. NO.	MATERIALS	MANUFACTURER/BRANDS OF MATERIALS/EQUIPMENT
	CABLES & ACCESSORIES	
1.	LV Wiring Cables (300 / 500 Volts)	Fast Cables, Pakistan Cables
2.	LV Power Cables (600 / 1000 Volts)	Fast Cables, Pakistan Cables
3.	High Voltage Cables(15 kV)	Fast Cables, Pakistan Cables
4.	MV Termination/Straight Jointing kit (Hot/Cold Termination)	Raychem, 3M
5.	CAT Cables	Corning
6.	Fire Resistant Cables	Belden, Prismian, Cavicel
7.	Glands, Lugs, Ferrules, Connectors	Cembre, Gewiss
8.	Cable Tagging/Labelling System	Cembre, Hellermanntyton
	PVC AND STEEL CONDUIT	
9.	Electrical PVC Conduit & Accessories	Dadex, Dura Flow
10.	Steel Conduit & Accessories	IIL,
	ELECTRICAL COMPONENTS	
11.	LV Circuit Breakers (MCB, MCCB, ELCB, ACB) (Schneider, ABB

12.	LV Magnetic Contactor, Starters & Thermal Overload Relay	Schneider, ABB
13.	Power Factor Capacitor	Schneider, ABB, Nokian, RTR, Shizuki
14.	LV Capacitor	Amber Capacitor, Entes, Nokian, Ducati, Schneider Electric
15.	PF Controller	Schneider, ABB, Shizuki
16.	Series Reactor	Nokian, Schneider Electric, ABB, GE, Shizuki
17.	Timer	GE, National / Panasonic, Finder, Fuji, Hanyong
18.	Push buttons and indication lights	GE, Maruyasu, Lovato, Fuji, Hanyong
19.	Current Transformer/Voltage Transformer	Entes, Revalco, Circutor, Sacci, Frer, FICO
20.	Measuring Instrument	Entes, Revalco, Circutor, Lovato, Schneider Electric, Hanyong
21.	Programmable Logic Controllers	Siemens, ABB, Schneider Electric
22.	VSS/ASS	Kraus & Naimer, Fuji, Hanyong
23.	HRC Fuses	Siba, ETI, Voltran
	TRANSFORMER	
24.	Oil Type Transformers (11/0.415 kV)	PEL
25.	Dry Type Transformers (11/0.415 kV)	PEL-IMEFY, Schneider, ABB
26.	LV Panel	Hussian & Co, Karimi Electromech, or Approved PARCO manufacturer's
27.	11 kV Panels	Siemens, PEL, Schneider Electric, ABB
28.	MV Surge Arrester	Siemens, PEL Schneider Electric, ABB
	LIGHTING FIXTURE & COMPONENTS	Note: 3 rd Party Test Report(s) shall be submitted from IEC accredited laboratories for verification of Quality of Light Fixtures submitted by the Contractor and minimum 3 years warranty shall be provided. This clause in applicable to items from Serial No. 28 to 36.

29.	Surface/recessed office luminaries	Philips (Signify), NVC, EAE, Ledvance, Opple
30.	Battens	Philips (Signify), NVC, EAE, Ledvance, Opple
31.	Downlights	Philips (Signify), NVC, EAE, Ledvance, Opple
32.	Exit Emergency Light Fixture	Hochiki, NVC, EAE, Ledvance, Escalux
33.	Lamps/LED chips	Source as approved by the "Engineer"
34.	Control gear/LED drivers	Source as approved by the "Engineer"
35.	Connectors/holders	Source as approved by the "Engineer"
36.	Solar Light Standalone/System	Leadsun, Gewiss
37.	Street Light	Philips (Signify), NVC, EAE, Ledvance
	SWITCHES & SOCKETS	
38.	Switches	MK, Schneider Electric, ABB, Legrand, Philips (Signify)
39.	Sockets	MK, Schneider Electric, ABB, Legrand, Philips (Signify)
40.	Dimmer / Fan Speed Controller	MK, Schneider Electric, ABB, Legrand, Philips (Signify)
41.	Connection Unit	MK, Schneider Electric, ABB, Legrand, Philips (Signify)
42.	Voice/TV/Data Outlets	MK, Schneider Electric, ABB, Legrand, Philips (Signify)
43.	Back Boxes	MK, Schneider Electric, ABB, Legrand, Philips (Signify)
44.	High Current Switches	MK, Schneider Electric, ABB, Legrand, Philips (Signify)
45.	Industrial Switches, Plugs and Sockets	Walther, GARO, Schneider, Gewiss
	DIESEL GENERATOR SET	Note: The Diesel Generator Suppliers shall have minimum 10 years of proven experience in selling and providing after sales services. The supplier shall show sizable frequency of DG set sales for a period of last 10 years for approval. This Clause is applicable to Serial No. 46.

46.	Couplers	Caterpillar, CPG (Cummins), Onis Visa, SDMO, FG-Wilson, Synergy (The set shall be from above brands and is subject to approval of verification of import source and proper documentation. The engine and alternator shall not be old than 12 months from the date of purchase. Principal warranty of 3 years/3000 hours shall be provided. Load Testing shall be performed as per specifications.
47.	Engines from 10 kVA upto 500 kVA ratings	Caterpillar, Cummins, Perkins, Volvo
48.	Engines from 500 kVA upto 2500 kVA	Caterpillar, Cummins , MTU, Mitsubishi, Kohler
49.	Alternator	Caterpillar, Stamford, Leroy Somer, Mecc Alte, Kohler
50.	Generator Module	Deepsea Electronics, Caterpillar, Cummins, Kohler
51.	ATS/AMF, Generator Panels	Refer to heading Electrical Panels in the List of Approved Manufacturer's.
	ELECTRONICS/COMPUTER EQUIPMENT	
52.	UPS	APC, Eaton, Vertiv
53.	Fire Alarm/Fighting System	Coordinate with Building Maintenance Department
54.	Public Address System	TOA, Bosch, Honeywell
55.	Burglar Alarm System	DSC, Texicom, Bosch, Honeywell
56.	CCTV System (Ultra / Top Range Series is acceptable)	Pelco, Bosch, Axis Communication, Infinova
57.	CATV	WISI, Scientific Atlanta
58.	Lightning Protection, Earthing System & Surge Protection (European Origin)	Wallis, Furse
59.	PABX	Panasonic
60.	Access Control System	Cavdax Gallaghev, Virdi, Salto
	COMPUTER NETWORK SYSTEM/COMPONENTS	
61.	Structured Cabling	Corning
62.	Ethernet Switches (Channelized Components + Smart Support with 2 years	CISCO or as mentioned in BoQ

Sign & Stamp of The Contractor

	principal warranty)	
	MISC MATERIALS	
63.	Construction Chemicals	Vandex, FEB, SIKA, Fosroc
64.	Cable Tray with accessories	Ashraf Industries, Electroline
65.	Street Lighting Poles	Jamal Pipes
66.	Power Supplies/Convertors	Siemens, ABB, PULS GmbH
67.	Industrial Plugs & Sockets	Walther, GARO, Schneider, Gewiss
68.	Junction Boxes (Polycarbonate DB)	HENSEL, Gewiss
69.	High Mast (up to 40 m)	Petit Jean, Metelogalva
70.	Ring Main Unit, MV Panels (Fixed Type Circuit Breaker)	Lucy Electric, Schneider Electric
71.	Ceiling Fan/Bracket Fan	Pak Fan, GFC, Royal, Yunas
72.	False Ceiling Fan	Voldam